


LUXURY MOTOR TOYS GARAGE CONDOMINIUM



65 OLDE CANAL WAY, GORHAM, MAINE

PROJECT INFORMATION

CIVIL ENGINEER
HALEY WARD
ATTN: JON WHITTEN, JR., PE
120 MAIN STREET, SUITE 132
SACO, MAINE 04072
T: 207.283.9151

DEVELOPER
GENX CAPITAL PARTNERS, LLC
ATTN: MARK McCLURE
2 COTTON STREET
PORTLAND, MAINE, 04101
T: 207.417.1218

UTILITY PROVIDERS
WATER & SEWER
PORTLAND WATER DISTRICT
225 DOUGLASS STRET
PO BOX 3553
PORTLAND, MAINE 04104

T: 207.774.5961


ELECTRIC CENTRAL MAINE POWER CO. 83 EDISON DRIVE AUGUSTA, MAINE 04330 T: 800.750.4000

PERMITS AND APPROVALS:

NRPA TIER 1 WETLAND ALTERATION PERMIT L-23520-39-A-N ACOE MAINE PROGRAMMATIC GENERAL PERMIT NAE-2007-1291 MAINE DOT TRAFFIC MOVEMENT PERMIT 01-00061-A-N SITE LOCATION OF DEVELOPMENT ACT PERMIT L-23520-TC-B-N

PLAN & DOCUMENT REFERENCES:

- A PLAN ENTITLED "SITE PLAN OF SHUCKS MAINE LOBSTER PROCESSING FACILITY", RECORDED WITH THE STATE OF MAINE
 REGISTRY OF DEEDS, BY SEBAGO TECHNICS, DATED SEPTEMBER 27,
 2017
- 2. A PLAN ENTITLED "AS-BUILT GRADING & UTILITY PLAN OF OLDE CANAL BUSINESS PARK", BY SEBAGO TECHNICS, DATED JANUARY 17, 2023.



NOT FOR CONSTRUCTION FEBRUARY 14, 2024



INDEX OF DRAWINGS

C000 COVER SHEET

C001 GENERAL NOTES, EROSION CONTROL, & LEGEND

V101 EXISTING CONDITIONS

C101 SITE & GRADING PLAN

C102 UTILITIES PLAN
C103 LANDSCAPING PLAN

04 PHOTOMETRIC PLAN

C105 EMERGENCY VEHICLE ACCESS PLAN

C501 SITE DETAILS - 1

C502 SITE DETAILS - 2

C503 SITE DETAILS - 3
C504 SITE DETAILS - 4

C505 SITE DETAILS -

13//3.0

BE INCIDENTAL TO THIS PROJECT.

- THE CONTRACTOR SHALL PROVIDE ALL LABOR, EQUIPMENT, AND MATERIALS AS REQUIRED TO PERFORM THE WORK AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS. ALL WORK SHALL BE COMPLETED IN ACCORDANCE WITH THE APPLICABLE FEDERAL, STATE AND LOCAL CODES.
- I. THE WORK SHALL INCORPORATE EROSION CONTROL MEASURES WHICH ARE COMPLIANT WITH THE LATEST VERSION OF "MAINE EROSION AND SEDIMENT CONTROL HANDBOOK FOR CONSTRUCTION: BEST MANAGEMENT
- . THE LOCATION, TYPE AND SIZE OF EXISTING PIPES, DUCTS, CONDUITS AND OTHER UNDERGROUND STRUCTURES SHOWN ON THE DRAWINGS ARE NOT WARRANTED TO BE EXACT NOR IS IT WARRANTED THAT ALL UNDERGROUND STRUCTURES ARE SHOWN. CONTRACTOR SHALL FIELD VERIFY ALL UTILITY LOCATIONS PRIOR TO COMMENCEMENT OF CONSTRUCTION. DEPTH OF SERVICES ARE UNKNOWN AND SHALL BE FIELD VERIFIED BY THE CONTRACTOR. EXCAVATING TEST PITS AS NECESSARY TO VERIFY UTILITY LOCATIONS AND DEPTHS SHALL
- THE CONTRACTOR SHALL COORDINATE ALL CONSTRUCTION WITH THE UTILITY COMPANIES, DIG SAFE, AND EMERGENCY SERVICES WHERE APPLICABLE. CONTRACTOR SHALL NOTIFY ALL UTILITIES PRIOR TO COMMENCING WORK TO ALLOW SUFFICIENT TIME TO LOCATE AND MARK THE LOCATION OF ALL BURIED UTILITIES. CONTRACTOR SHALL ALSO CONTACT "DIG SAFE", TELEPHONE NO 800-225-4977. REPAIR OF ANY DAMAGED UTILITY WILL BE INCIDENTAL TO THIS PROJECT.
- . CONTRACTOR SHALL MAINTAIN TRAFFIC IN A SAFE MANNER AT ALL TIMES DURING CONSTRUCTION. THE CONTRACTOR SHALL MAKE EVERY EFFORT TO MAINTAIN CONTINUOUS TRAFFIC FLOW DURING CONSTRUCTION. THE ROADS SHALL NOT BE CLOSED TO TRAFFIC WITHOUT PERMISSION FROM THE OWNER.
- . THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT EQUIPMENT FLUIDS FROM REACHING ANY WATER COURSE. ANY INADVERTENT FLUID DISCHARGES SHALL BE IMMEDIATELY CLEANED FROM THE WATERS USING WHATEVER MEANS NECESSARY, AS DETERMINED BY THE ENGINEER.
-). RESTORE ALL AREA DISTURBED BY CONTRACTOR'S OPERATIONS TO ORIGINAL CONDITION (GRAVEL, PAVEMENT, GRASS, ETC.) UNLESS NOTED OTHERWISE ON PLANS. RESTORATION OF GRAVEL ROAD AND DRIVEWAY SURFACES AND LAWNS DAMAGED BY CONTRACTOR SHALL BE INCIDENTAL TO THE PROJECT.
- 10. EXISTING FACILITIES AND IMPROVEMENTS (I.E. TREES, LIGHT POLES, SIGNS, ETC.) SHALL BE REMOVED AND REPLACED OR PROTECTED AS REQUIRED DURING CONSTRUCTION. THE ASSOCIATED COSTS ARE INCIDENTAL TO THE PROJECT. BRACING OF UTILITY POLES, WHERE REQUIRED, SHALL BE INCIDENTAL TO THE PROJECT AND NO SEPARATE PAYMENT SHALL BE MADE.
- 11. IT IS ASSUMED THAT THERE IS NO BEDROCK WITHIN THE PROJECT LIMITS, BUT A PROVISION WITHIN THE BID FORM PROVIDES FOR A UNIT COST IN THE EVENT THAT BEDROCK OR ROCKS EXCEEDING 2 CY IN VOLUME ARE ENCOUNTERED. PAYMENT WILL BE IN A UNIT PRICE BASIS AS INDICATED IN THE SPECIFICATIONS.
- 12. RESTRICT ACCESS TO SITE THROUGH THE USE OF APPROPRIATE SIGNAGE, GATES, BARRIERS, FENCES, ETC. SITE SHALL BE LEFT WITH APPROPRIATE SAFETY MEASURES IN PLACE DURING NON-WORKING HOURS. NO TRENCH SHALL BE LEFT OPEN DURING NON-WORKING HOURS. SITE SAFETY IS THE RESPONSIBILITY OF CONTRACTOR. DURING BOTH WORKING AND NON-WORKING HOURS.
- 13. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY CONSTRUCTION PERMITS. PERMIT APPLICATIONS SHALL BE SUBMITTED WITH ADEQUATE TIME SO AS NOT TO DELAY CONSTRUCTION.
- 14. EXISTING FLOWS VARY SIGNIFICANTLY FROM HOUR TO HOUR AND SEASON TO SEASON. PEAK FLOWS ARE INFLUENCED BY RAIN EVENTS AND GROUNDWATER DEPTHS. THE CONTRACTOR SHALL CONDUCT HIS OPERATIONS TO BE PREPARED FOR THESE VARIABLE FLOW CONDITIONS.
- 15. ALL WORK OF ITEMS SCHEDULED FOR EITHER REMOVAL, DISPOSAL, PLUG, OR ABANDON SHALL BE PERFORMED AS INDICATED ON THE DRAWINGS AND SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT. NO OTHER PAYMENT SHALL BE MADE.
- 16. ALL FINISH SURFACES SHALL BE INSTALLED TO PROMOTE POSITIVE DRAINAGE. IN NO WAY SHALL THE NEW FINISH SURFACES AND CATCH BASINS CREATE DRAINAGE PROBLEMS THAT DID NOT EXIST PRIOR TO
- 17. CONTRACTOR SHALL BE RESPONSIBLE FOR THE LAYOUT OF ALL PROPOSED WORK AS SHOWN ON DRAWINGS.
- 18. HOURS FOR THE PROJECT WILL BE MONDAY THROUGH FRIDAY, FROM 7:00 AM TO 7:00 PM, UNLESS OTHERWISE AUTHORIZED BY THE OWNER AND TOWN OF GORHAM.
- 19. THE CONTRACTOR SHALL PROVIDE A SEDIMENT BASIN FOR ALL WATER PUMPED FROM EXCAVATIONS. BASIN SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH THE "MAINE EROSION AND SEDIMENT HANDBOOK FOR CONSTRUCTION: BEST MANAGEMENT PRACTICES". THE CONTRACTOR SHALL SUBMIT FOR REVIEW/APPROVAL PRIOR TO BEGINNING ANY PROJECT WORK.

EROSION CONTROL NOTES

- ALL SEDIMENTATION AND EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE MAINE EROSION AND SEDIMENTATION CONTROL BMPS, PUBLISHED BY THE BUREAU OF LAND AND WATER QUALITY, MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION, LATEST EDITION.
- SILT FENCE WILL BE INSPECTED. REPLACED AND/OR REPAIRED IMMEDIATELY FOLLOWING ANY SIGNIFICANT. RAINFALL OR SNOW MELT OR LOSS OF SERVICEABILITY DUE TO SEDIMENT ACCUMULATION. AT A MINIMUM, ALL EROSION CONTROL DEVICES WILL BE OBSERVED WEEKLY.
- B. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT WILL BE RETURNED TO CONSTRUCTION SITE.
- I. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE STABILIZED BY A SUITABLE GROWTH OF GRASS. ONCE A SUITABLE GROWTH OF GRASS HAS BEEN OBTAINED, ALL TEMPORARY EROSION CONTROL ITEMS SHALL BE REMOVED BY THE CONTRACTOR. ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THEY ARE REMOVED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED, SEEDED, AND MULCHED IMMEDIATELY.
- ALL DISTURBED AREAS WILL BE SEEDED WITH 2.5 LBS. RED FESCUE AND 0.5 LBS. RYE GRASS PER 1,000 SQUARE FEET AND MULCHED AT A RATE OF 90 LBS. PER 1,000 SQUARE FEET OR EQUIVALENT APPLICATION OF SEED AND
- 6. A SUITABLE BINDER SUCH AS CURASOL OR TERRTACK WILL BE USED ON THE HAY MULCH FOR WIND CONTROL.
- 7. IF FINAL SEEDING OF DISTURBED AREAS IS NOT COMPLETED BY SEPTEMBER 15th OF THE YEAR OF CONSTRUCTION, THEN ON THAT DATE THESE AREAS WILL BE GRADED AND SEEDED WITH WINTER RYE AT THE RATE OF 112 POUNDS PER ACRE OR 3 POUNDS PER 1000 SQUARE FEET. THE RYE SEEDING WILL BE PRECEDED BY AN APPLICATION OF 3 TONS OF LIME AND 800 LBS. OF 10-20-20 FERTILIZER OR ITS EQUIVALENT. MULCH WILL BE APPLIED AT A RATE OF 90 POUNDS PER 1000 SQUARE FEET.
- 8. IF THE RYE SEEDING CANNOT BE COMPLETED BY OCTOBER 1st OR IF THE RYE DOES NOT MAKE ADEQUATE GROWTH BY DECEMBER 1st, THEN ON THOSE DATES, HAY MULCH WILL BE APPLIED AT 150 POUNDS PER 1000
-). ALL CATCH BASINS ARE TO BE PROTECTED BY STRAW BALE OR SILTFENCE IN ACCORDANCE WITH SECTION B-3 STORM DRAIN INLET PROTECTION OF THE MAINE BMP HANDBOOK. SURROUNDING AREAS CAN BE EXCAVATED OR LEFT LOW AS A SEDIMENT TRAP. CURB INLETS SHALL BE PROTECTED BY GUTTERGATORS, OR APPROVED
- 10. INTERIOR SILT FENCES ALONG CONTOUR DIVIDING FLAT AND STEEP SLOPES, AREAS WITH DIFFERENT DISTURBANCE SCHEDULES, AROUND TEMPORARY STOCKPILES OR IN OTHER UNSPECIFIED POSSIBLE CIRCUMSTANCES SHOULD BE CONSIDERED BY THE CONTRACTOR. THE INTENT OF SUCH INTERIOR SILT FENCES IS TO LIMIT SEDIMENT TRANSPORT WITHIN THE SITE TOWARD THE PROTECTED CATCH BASIN INLETS TO MINIMIZE SEDIMENT REMOVAL REQUIRED BY THE EROSION CONTROL NOTE 9 PROTECTIONS AND EXTEND LIFE OF SUCH
- 1 CONSTRUCTION OVERSIGHT THE CONTRACTOR WILL RETAIN THE SERVICES OF A PROFESSIONAL ENGINEER TO INSPECT THE CONSTRUCTION AND STABILIZATION OF ALL STORMWATER MANAGEMENT STRUCTURES. IF NECESSARY, THE INSPECTING ENGINEER WILL INTERPRET THE POND'S CONSTRUCTION PLAN FOR THE CONTRACTOR. ONCE ALL STORMWATER MANAGEMENT STRUCTURES ARE CONSTRUCTED AND STABILIZED, THE INSPECTING ENGINEER WILL NOTIFY THE DEPARTMENT IN WRITING WITHIN 30 DAYS TO STATE THAT THE POND HAS BEEN COMPLETED. ACCOMPANYING THE ENGINEER'S NOTIFICATION MUST BE A LOG OF THE ENGINEER'S INSPECTIONS GIVING THE DATE OF EACH INSPECTION, THE TIME OF EACH INSPECTION, AND THE ITEMS INSPECTED ON EACH VISIT, AND INCLUDE ANY TESTING DATA OR SIEVE ANALYSIS DATA OF EVERY MINERAL SOIL AND SOIL MEDIA SPECIFIED IN THE PLANS AND USED ON SITE.
- 12. LOT GRADING AND DRIVEWAY LOCATION: INSPECTIONS BY A PROFESSIONAL ENGINEER WILL CONSIST OF A VISIT TO THE SITE PRIOR TO CONSTRUCTION TO CONSULT WITH THE EARTHWORK CONTRACTOR AND A POST CONSTRUCTION MEETING TO CONFIRM GRADING ON LOTS AND FOR ALL DRIVEWAYS TO ENSURE RUNOFF IS DIRECTED ACCORDING TO PLANS AND TO OVERSEE THE RE-STABILIZATION OF THE LOT INTO A VEGETATED COVER
- 13. BASIC STANDARDS EROSION CONTROL MEASURES: MINIMUM EROSION CONTROL MEASURES WILL NEED TO BE IMPLEMENTED AND THE CONTRACTOR WILL BE RESPONSIBLE TO MAINTAIN ALL COMPONENTS OF THE EROSION CONTROL PLAN UNTIL THE SITE IS FULLY STABILIZED. HOWEVER, BASED ON SITE AND WEATHER CONDITIONS DURING CONSTRUCTION, ADDITIONAL EROSION CONTROL MEASURES MAY NEED TO BE IMPLEMENTED. ALL AREAS OF INSTABILITY AND EROSION MUST BE REPAIRED IMMEDIATELY DURING CONSTRUCTION AND NEED TO BE MAINTAINED UNTIL THE SITE IS FULLY STABILIZED OR VEGETATION IS ESTABLISHED. A CONSTRUCTION LOG MUST BE MAINTAINED FOR THE EROSION AND SEDIMENTATION CONTROL INSPECTIONS AND MAINTENANCE
- 14. CONTRACTOR WILL BE RESPONSIBLE FOR FOLLOWING PROCEDURES FOUND IN THE "MAINE EROSION AND SEDIMENT CONTROL PRACTICES FIELD GUIDE FOR CONTRACTORS" (PUBLISHED MARCH 2015). THE PUBLICATION CAN BE FOUND AT: HTTP://WWW.MAINE.GOV/DEP/LAND/EROSION/ESCBMPS/INDEX.HTML


PERMITTING NOTES


1. PROJECT IS SUBJECT TO THE TERMS AND CONDITIONS OF A MAJOR AMENDMENT SITE PLAN APPROVAL FROM THE TOWN OF GORHAM. THE CONSTRUCTION WILL BE GOVERNED BY THE TOWN OF GORHAM LAND USE

PROJECT, AND INCLUDE COSTS AS NECESSARY TO COMPLY WITH THE CONDITIONS OF THESE PERMITS.


- ORDINANCE. 2. EXISTING PERMITS AND APPROVALS GOVERNING USE OF THE SUBDIVISION:
- NRPA TIER 1 WETLAND ALTERATION PERMIT L-23520-39-A-N
- ACOE MAINE PROGRAMMATIC GENERAL PERMIT NAE-2007-1291 MAINE DOT TRAFFIC MOVEMENT PERMIT 01-00061-A-N
- 3. THE CONTRACTOR SHALL REVIEW THE ABOVE REFERENCED PERMITS PRIOR TO SUBMITTING A BID FOR THIS

SITE LOCATION OF DEVELOPMENT ACT PERMIT L-23520-TC-B-N







SILT SOCK DETAIL




BANK STABILIZATION DETAIL



EROSION CONTROL MIX BERM DETAIL NTS (MAY BE USED AS AN ALTERNATE TO SILT FENCE)



CONSTRUCTION DEBRIS OR REPROCESSED WOOD PRODUCTS).



SEDIMENT SACK INLET PROTECTION DETAIL

STABILIZED CONSTRUCTION ENTRANCE DETAIL

FILTER SURFACE VWW.HALEYWARD.COM

LEGEND: ITEMS SHOWN MAY NOT APPEAR ON PLANS DESCRIPTION EXISTING PROPOSED PROPERTY LINE BENCHMARK SURVEY STATION IRON PIN DRILL HOLE BOUND TEST PIT SEWER MANHOLE GAS VALVE UTILITY POLE **GUY ANCHOR** ELECTRICAL MANHOLE TRANSFORMER PULLBOX WELL WATER VALVE WATER SHUTOFF **HYDRANT** AIR RELIEF VALVE DRAINAGE MANHOLE CATCH BASIN **CURB INLET** PARKING LIGHT FLOOD LIGHT SITE LIGHT SIGN 0 00 TRASH CAN FLAGPOLE \sim MONITORING WELL EDGE OF GRAVEL _____ EDGE OF PAVEMENT CURBING MAJOR FOOT CONTOUR ----- 100 ----- 100 ----- MINOR FOOT CONTOUR WATERLINE STORM DRAIN UNDER DRAIN SANITARY SEWER FORCE MAIN _____ FM____ OVERHEAD UTILITIES ----- OHU-----UNDERGROUND UTILITIES ----- UGE ---------- UGU-----GAS LINE ——— GAS——— CHAIN LINK FENCE

GUARDRAIL SILT FENCE TREE LINE **GRAVEL SURFACE** PAVED SURFACE CONCRETE SURFACE

عللد WETLANDS

RIPRAP


BUILDING FOOTPRINT

One Merchants Plaza, Suite 7

NOT FOR CONSTRUCTION

GENX CAPITAL PARTNERS, LLC 2 COTTON STREET, PORTLAND, MAINE **LUXURY MOTOR TOYS** 65 OLDE CANAL WAY, GORHAM, MAINE

NOTES & LEGEND



DJO/AWG

13773.003


Bangor, Maine 0440


NTS


207.989.4824


(MAY BE USED AS AN ALTERNATE TO HAY BALES)


SECTION














MAPTECH® USGS TOPOGRAPHIC SERIES™, ©MAPTECH®, INC. 978-933-3000 WWW.MAPTECH.COM/TOPO

SHRUB PLANTING DETAIL

1) STAKING AT CONTRACTOR'S DISCRETION

2) ON TREES BELOW 3" CAL. USE WOOD STAKES 3) ON TREES 4" CAL. OR GREATER USE GUYING

4) IF GUYING CABLES USE 3 PER TREE MIN. AS NEEDED

5) FOR PRUNING, SEE SPECIFICATIONS
6) REMOVE ALL OF WIRE BASKETS ON ROOTBA


CHAFING GUARDS, 1 1/2" **EQUALLY SPACED, NOT HIGHER** TURNBUCKLE AS NEEDED-THAN 3/4 TREE HT., DRIVEN INTO THE GROUND AND PLUMB CUT AND REMOVE BURLAI - SET ROOT FLAIR 1" HIGHER FROM TOP 1/3 OF ROOT THAN FINISHED GRADE NON-BIODEGRADEABLE, - 2" MULCH AS SPECIFIED, DO NOT PUT MULCH AGAINST THE BASE OF TREE. - FINISHED GRADE TREE ANCHOR - 6' OR TWICE THE WIDTH OF THE ROOTBALL. WHICHEVER IS GREATER. PREPARE SOIL AS SPECIFIED — ☐ TAMP BASE UNDER

ROOT BALL

TREE PLANTING DETAIL

PLANTING NOTES

- 1. ALL MATERIALS SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE AMERICAN ASSOCIATION OF
- 2. IN THE CASE OF ANY DISCREPANCIES BETWEEN SPACES AND QUANTITIES CALLED OUT IN THE PLANTING KEY AND THOSE SHOWN ON THE PLAN, QUANTITIES AND SPECIES SHOWN ON THE PLAN SHALL OVER-RIDE.
- ALL PLANTS SUBJECT TO APPROVAL BY LANDSCAPE ARCHITECT. LANDSCAPE ARCHITECT RESERVES THE RIGHT TO REJECT ANY PLANTINGS THAT DO NOT CONFORM TO THE DRAWINGS OR SPECIFICATIONS OUTLINED HEREIN. 5. EXISTING TREES TO REMAIN SHALL BE PROTECTED BY PVC FENCING PLACED AT THE DRIP-LINE OR AS SHOWN ON THE PLANS TO PREVENT DAMAGE AND COMPACTION OF THE ROOT SYSTEM. NO GRADING, SOIL DISTURBANCE, OR STORAGE OF MATERIALS OR EQUIPMENT SHALL OCCUR WITHIN THE DRIP-LINE UNLESS OTHERWISE SHOWN ON PLANS. ANY EXCAVATION WITHIN SUCH AREAS SHALL BE PERFORMED BY HAND TO AVOID DAMAGE OF THE ROOT
- 6. NO PLANT SHALL BE PUT INTO THE GROUND BEFORE ROUGH GRADING HAS BEEN FINISHED AND APPROVED BY THE LANDSCAPE ARCHITECT OR OWNER'S REPRESENTATIVE. FINISH GRADE OF PLANTINGS SHALL MATCH ADJACENT FINISH GRADE UNLESS OTHERWISE NOTED ON DRAWINGS OR DIRECTED AND/OR APPROVED BY THE
- EARTHLIFE BY NEW ENGLAND ORGANICS, FALMOUTH, ME TEL 207-781-5011, OR APPROVED EQUAL. THE PREPARED SOIL SHALL BE SPREAD UNIFORMLY, AT A 12 INCH MINIMUM DEPTH IN PLANTING BEDS AND 4" IN AREAS TO BE SEEDED, AS SHOWN ON PLANS. 8. LANDSCAPE ARCHITECT SHALL APPROVE FINAL PLACEMENT OF ALL PLANT MATERIALS AND RESERVES THE RIGHT
- TO MAKE FIELD ADJUSTMENTS TO PLANTINGS AS NECESSARY.
- ALL PLANTS SHALL BE SET PLUMB UNLESS OTHERWISE SPECIFIED. 10. ALL PLANTINGS SHALL BE TOPPED WITH A MINIMUM OF 3" OF WELL COMPOSTED, DARK PINE BARK MULCH. SEEDED AREAS SHALL BE MULCHED WITH SHREDDED STRAW OR APPROVED MULCH.
- 11. ALL DISTURBED AREAS NOT OTHERWISE PLANTED SHALL BE SEEDED AS SHOWN ON THE PLANS OR AS APPROVED. SEEDING AREAS SHALL BE LIGHTLY MULCHED WITH A LAYER OF CLEAN, WEED-FREE STRAW.
- 12. ALL PLANTS SHALL BE WATERED THOROUGHLY TWICE DURING THE FIRST 24-HOUR PERIOD AFTER PLANTING. ALL PLANTS SHALL BE WATERED AS REQUIRED THEREAFTER TO ENSURE SURVIVAL AND GROWTH THROUGH THE
- 13. SEEDED LAWN AREAS SHALL BE WATERED REGULARLY AND MAINTAINED THROUGH ESTABLISHMENT AND/OR
- 14. PLANT MATERIAL SHALL BE GUARANTEED BY THE CONTRACTOR FOR A PERIOD OF ONE YEAR FROM THE DATE OF INSTALLATION. DURING THE ONE YEAR GUARANTEE, THE CONTRACTOR SHALL REPLACE, IN KIND, ANY DEAD, DISEASED, OR SUBSTANDARD PLANT MATERIAL AT NO COST TO THE OWNER. 15. SATISFACTORY CONSERVATION COVER: AT END OF MAINTENANCE PERIOD, A HEALTHY, WELL-ROOTED, DENSE
- COVER (90%) OF THE APPROPRIATE SPECIES HAS BEEN ESTABLISHED. 16. THE CONTRACTOR SHALL RECEIVE FINAL ACCEPTANCE FROM THE OWNER FOLLOWING THE ONE YEAR GUARANTEE, PROVIDED THE PROVISIONS OF THE PLANT GUARANTEE HAVE BEEN SATISFACTORILY MET.



NOT FOR CONSTRUCTION



2 COTTON STREET, PORTLAND, MAINE **LUXURY MOTOR TOYS** 65 OLDE CANAL WAY, GORHAM, MAINE

GENX CAPITAL PARTNERS, LLC


LANDSCAPING PLAN


2024.02.12


DJO/AWG


13773.003


C103






















- PIPE DIAMETERS MAY VARY, SEE TYPICAL PIPE TRENCH DETAIL, THIS SHEET.


WHERE 30' MINIMUM ANGLE BETWEEN SEWER CONNECTION AT THE SEWER MAIN AND THE VERTICAL CANNOT BE MAINTAINED, PROVIDE A PRECAST SEWER CHIMNEY. · IF STAKE IS CUT OFF FLUSH OR SLIGHTLY BELOW GRADE, PROVIDE MIN. OF TWO 18d. GALV. SPIKES DRIVEN INTO TOP OF 2" x 4" TO PROVIDE METAL DETECTABILITY.

HORIZONTAL SEWER CONNECTION




TRENCH SECTION N.T.S.





INSULATION DETAIL "B" N.T.S.



FILE SEW-TNCH-DET

GENX CAPITAL PARTNERS, LLC 2 COTTON STREET, PORTLAND, MAINE **LUXURY MOTOR TOYS** 65 OLDE CANAL WAY, GORHAM, MAINE SITE DETAILS NTS 2024.02.12

NOT FOR CONSTRUCTION

HALEY WARD

DJO/AWG

13773.003

C505

Bangor, Maine 04401 207.989.4824

DATE DESCRIPTION

WWW.HALEYWARD.COM

WHITTEN, JR. No. 10414 CENSE SONAL EN

1 OF 1