


ROBIE STREET SUBDIVISION



LEGEND EXISTING		PROPOSED
	PROPERTY LINE/R.O.W.	
	ABUTTER LINE/R.O.W. DEED LINE/R.O.W.	
	TIE LINE	
· ·	SETBACK EASEMENT	
	BUFFER	
	FLOODPLAIN FLOODWAY	
	CENTERLINE	
	MONUMENT	
Ø	IRON PIPE/ROD DRILL HOLE	•
C1/L1	DEED CALL	C
C1/L1	CURVE/LINE NO. SOILS	C1/L1
	ZONE LINE	
	ZONE LINE ON PL	
BENCHMARK DESCRIPTION WITH ELEVATION	BENCHMARK	
	SURVEY CONTROL	
	TEST PIT	
MW-1	MONITORING WELL	
⊖ B-1	BORING BUILDING	
	DECK/STEPS/ OVERHANG	
	OVERHANG EDGE WETLAND	
<u>ullı</u>	WETLANDS	
~ 	UPLANDS STREAM	
AVVVV	LEDGE	
	PAVEMENT SAWCUT EDGE CONCRETE	A
	PAVEMENT PAINT	
	EDGE GRAVEL CURB LINE	
	EDGE OF WATER	
	TREELINE	
120118 ×120.00	SPOT GRADE	
o	CHAIN LINK FENCE	o
	BARB WIRE FENCE STOCKADE FENCE	×
	GUARD RAIL	<u> </u>
for the second	RETAINING WALL	
Land Contraction of the second s	DECIDUOUS TREE	X
	CONIFEROUS TREE	(x)
	MULCH LINE	
0 	BOLLARD SIGN	• ••
+ $+$ $+$ $+$	RAILROAD	
G GV ⊠	GAS GAS GATE VALVE	G GV
GM	GAS METER	
G	GAS MANHOLE	
W 	WATER WATER GATE VALVE	
$\bigvee_{NS^{O}}$	WATER SHUT OFF	42°
- Ç-	HYDRANT WATER MANHOLE	.
(W) (W)	WATER MANHOLE WELL	\odot
S	SANITARY SEWER	s
	FORCE MAIN	FM
©	SANITARY MANHOLE	
	UNDER DRAIN	UD
\bigcirc	DRAINAGE MANHOLE	(\bullet)
	CATCH BASIN	
-	OVERHEAD UTILITY	OHU
UGU	UNDERGROUND UTILITY	
T E	TRANSFORMER PAD ELECTRICAL MANHOLE	E E
	ELECTRIC METER	S
H		
T X	TELEPHONE MANHOLE LIGHT POLE	: ★●■★
-0-	UTILITY POLE	- / I X
(GUY WIRE DRAINAGE DITCH	
	EROSION CONTROL	
	BLANKET FILTER BARRIER	FB
}}}<u></u>}}	RIPRAP	
	CHECK DAM	
	INLET PROTECTION BOULDER	Å
	VEGETATED BUFFER	
	STORMWATER	
	BASIN/POND	

GENERAL NOTES

	MARCH 6, 2019 AND RECORDED A BOOK 35515, PAGE 90.	T THE CUMBERLAND COU	INTY REGISTRY	OF DEEDS (CCRD) II
<u>.</u>	THE PROPERTY IS SHOWN AS LOT TOWN OF GORHAM TAX MAP 25, L THE URBAN RESIDENTIAL (UR) AN SPACE AND BULK CRITERIA FOR T	OT 20 ON THE TOWN OF (D SUBURBAN RESIDENTI)	GORHAM TAX MA AL (SR) DISTRIC	AP 27 AND IS LOCAT T.
	W	ATERED/SEWERED	UNSEWERED	<u>(SR)</u>
	NET RESIDENTIAL DENSITY:	10,000 SQ.FT	20,000 SQ.FT.	40,000 SQ.FT
	MINIMUM LOT SIZE:	10,000 SQ.FT.	20,000 SQ.FT.	60,000 SQ.FT.
	MINIMUM STREET FRONTAGE:	80 FEET	80 FEET	200 FEET*
	MINIMUM FRONT YARD:	25 FEET	25 FEET	50 FEET: LOCAL ST 70 FEET: ARTERIA
	MINIMUM SIDE YARD:	15 FEET*	15 FEET*	20 FEET
	MINIMUM REAR YARD:	15 FEET*	15 FEET*	20 FEET
	MAXIMUM BUILDING HEIGHT:	NONE	NONE	NONE
	MAXIMUM BUILDING COVERAGE:	25%	25%	
	*	SEE ORDINANCE FOR I	MORE PARTICUL	AR INFORMATION.
.	TOTAL AREA OF PARCEL IS APPRO A. BOUNDARY AND TOPOGRAPHI PERFORMED BY SEBAGO TECH METHODS SUPPLEMENTED WIT WERE EMPLOYED IN THE COLL	C INFORMATION SHOWN INICS, INC., IN MAY, 2022. TH AERO-GEOMATIC/SUAS	TRADITIONAL S	URVEY MEANS AND GRAMMETRY & LIDA
	B. BOUNDARY RETRACEMENT OF BASED SOLELY UPON PLAN RE		I OF THE PROJE	CT PARCEL HEREO
	C. MONUMENTATION FOUND ON WITH RTK/GPS.	THE EASTERN PORTION (OF THE LOCUS F	ARCEL WAS LOCAT
j.	 PLAN REFERENCES: A. "STANDARD BOUNDARY SURVE COUNTY, MAINE" FOR FREDERI AND RECORD AT (CCRD) IN BOO B. "PLAN OF PRIVATE WAY WHISP 2006 AND RECORDED AT (CCRD C. "STANDARD BOUNDARY SURVE ELIZABETH DOWNS BY BH2M DA D. "SUBDIVISION PLAN OF BRAMBI SEBAGO TECHNICS DATED APP 	CK ROBIE, JR. BY ROSS E OK 200, PAGE 295. ERING PINES LANE" FOR D) IN BOOK 206, PAGE 638 EY & PRIVATE WAY PLAN ATED JULY 2001AND REC LE WOOD LANE SUBDIVIS	SOUNDARY SUR SUSAN & JOCK I TOPPAN DRIVE" ORDED AT (CCR ION" FOR GREG	VEYS DATED JULY 2 ROBIE, BY BH2M ON FOR HOWARD & D) IN BOOK 202, PAG ORY MCCORMACK
j.	ALL WORK SHALL CONFORM TO T	HE APPLICABLE CODES A	ND ORDINANCE	S.
	CONTRACTOR SHALL VISIT THE SI AFFECTING THE PROPOSED WORI CONTRACTOR SHALL BE RESPONS DOCUMENTS, FIELD CONDITIONS ACCOMPLISHED AS SHOWN PRIOF SHALL BE BROUGHT TO THE ATTE WORK.	K AND SHALL MAKE PRON SIBLE FOR FAMILIARIZING AND DIMENSIONS AND CO R TO PROCEEDING WITH	VISIONS AS TO T HIM OR HERSE DNFIRMING THA CONSTRUCTION	HE COST THEREOF. ELF WITH ALL CONTF T THE WORK MAY BI I. ANY DISCREPANC
i.	CONTRACTOR SHALL NOTIFY ENG ARE NOT FOUND IN THE FIELD.	INEER OF ALL PRODUCT	S OR ITEMS NOT	ED AS "EXISTING" W
).	PROVIDE ALL EQUIPMENT AND MA RECOMMENDATIONS AND OWNER INDICATED OR WHERE LOCAL COD	S REQUIREMENTS UNLE	SS SPECIFICALL	Y OTHERWISE
0.	CONTRACTOR SHALL VERIFY ALL FABRICATION AND ERECTION OF A TO THE ATTENTION OF THE ENGIN	ANY MATERIAL. ANY UNU		
1.	CONTRACTOR SHALL CLEAN AND STREETS, SIDEWALKS, ADJACENT			
2.	CONTRACTOR SHALL INCORPORA EXISTING STRUCTURES, PHYSICA CONSTRUCTION. CONTRACTOR SI DIRECTED BY DESIGN DRAWINGS.	L FEATURES, AND MAINT, HALL RESTORE ALL AREA	AIN SITE STABIL	ITY DURING
3.	SITE CONTRACTOR SHALL OBTAIN	ALL REQUIRED PERMITS	PRIOR TO CON	STRUCTION.
4.	ALL EROSION AND SEDIMENT CON "MAINE EROSION AND SEDIMENT ON WATER QUALITY OF THE MAINE DI OR LATEST EDITION. IT SHALL BE OF THE EROSION CONTROL PLAN	CONTROL BMPS" PUBLISH EPARTMENT OF ENVIRON THE RESPONSIBILITY OF	HED BY THE BUR	REAU OF LAND AND CTION, OCTOBER 2
5.	THE CONTRACTOR IS HEREBY CAU ON FIELD OBSERVATIONS BY THE COMPANIES. THE INFORMATION IS CONTRACTOR SHALL CONTACT DI (30) DAYS PRIOR TO COMMENCEM AND VERTICAL LOCATION OF ALL	SURVEYOR AND BY INFO S NOT TO BE RELIED ON A IG SAFE (811) AT LEAST T IENT OF EXCAVATION OR	RMATION PROV AS BEING EXACT HREE (3) BUT NO	IDED BY UTILITY OR COMPLETE. TH DT MORE THAN THIF
6.	CONTRACTOR SHALL BE AWARE T THE DIG. WHEN NOTIFIED, DIG SAI AREA. CONTRACTOR IS RESPONS DIRECTLY. NON-MEMBER UTILITIE AND SMALL LOCAL UTILITIES, AS V	FE WILL ADVISE CONTRA IBLE FOR IDENTIFYING A S MAY INCLUDE TOWN OI	CTOR OF MEMBI ND CONTACTING R CITY WATER A	ER UTILITIES IN THE S NON-MEMBER UTIL
7.	CONTRACTORS SHALL BE RESPON 3360-A. IT SHALL BE THE RESPONS APPROPRIATE UTILITIES TO OBTA UTILITIES WHICH CONFLICT WITH UTILITY CONFLICT ARISES, THE CO MUNICIPALITY AND APPROPRIATE RELOCATION.	SIBILITY OF THE CONTRA IN AUTHORIZATION PRIO THE PROPOSED IMPROVI ONTRACTOR SHALL IMME	CTOR TO COOR R TO RELOCATIO EMENTS SHOWN DIATELY NOTIFY	DINATE WITH THE ON OF ANY EXISTING NON THESE PLANS. Y THE OWNER, THE

- 18. ALL PAVEMENT MARKINGS AND DIRECTIONAL SIGNAGE SHOWN ON THE PLAN SHALL CONFORM TO THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD) STANDARDS.
- 19. ALL PAVEMENT JOINTS SHALL BE SAWCUT PRIOR TO PAVING TO PROVIDE A DURABLE AND UNIFORM JOINT.
- 20. NO HOLES, TRENCHES OR STRUCTURES SHALL BE LEFT OPEN OVERNIGHT IN ANY EXCAVATION ACCESSIBLE TO THE PUBLIC OR IN PUBLIC RIGHTS-OF-WAY.
- 21. IMMEDIATELY UPON COMPLETION OF CUTS/FILLS, THE CONTRACTOR SHALL STABILIZE DISTURBED AREAS IN ACCORDANCE WITH EROSION CONTROL NOTES AND AS SPECIFIED ON PLANS.
- 22. THE CONTRACTOR SHALL BE FULLY AND SOLELY RESPONSIBLE FOR THE REMOVAL, REPLACEMENT AND RECTIFICATION OF ALL DAMAGED AND DEFECTIVE MATERIAL AND WORKMANSHIP IN CONNECTION WITH THE CONTRACT WORK. THE CONTRACTOR SHALL REPLACE OR REPAIR AS DIRECTED BY THE OWNER ALL SUCH DAMAGED OR DEFECTIVE MATERIALS WHICH APPEAR WITHIN A PERIOD OF ONE YEAR FROM THE DATE OF SUBSTANTIAL COMPLETION.
- 23. ALL WORK PERFORMED BY THE GENERAL CONTRACTOR AND/OR TRADE SUBCONTRACTOR SHALL CONFORM TO THE REQUIREMENTS OF LOCAL, STATE OR FEDERAL LAWS, AS WELL AS ANY OTHER GOVERNING REQUIREMENTS. WHETHER OR NOT SPECIFIED ON THE DRAWINGS.
- 24. WHERE THE TERMS "APPROVED EQUAL", "OTHER APPROVED", "EQUAL TO", "ACCEPTABLE" OR OTHER GENERAL QUALIFYING TERMS ARE USED IN THESE NOTES, IT SHALL BE UNDERSTOOD THAT REFERENCE IS MADE TO THE RULING AND JUDGEMENT OF SEBAGO TECHNICS, INC.
- 25. THE GENERAL CONTRACTOR SHALL PROVIDE ALL NECESSARY PROTECTION FOR THE WORK UNTIL TURNED OVER TO THE OWNER.
- 26. THE GENERAL CONTRACTOR SHALL MAINTAIN A CURRENT AND COMPLETE SET OF CONSTRUCTION DRAWINGS ON SITE DURING ALL PHASES OF CONSTRUCTION FOR USE OF ALL TRADES.
- 27. THE CONTRACTOR SHALL TAKE FULL RESPONSIBILITY FOR ANY CHANGES AND DEVIATION OF APPROVED PLANS NOT AUTHORIZED BY THE ARCHITECT/ENGINEER AND/OR CLIENT/OWNER.
- 28. DETAILS ARE INTENDED TO SHOW END RESULT OF DESIGN. ANY MODIFICATION TO SUIT FIELD DIMENSION AND CONDITION SHALL BE SUBMITTED TO THE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ANY WORK.

THE RECORD OWNER OF THE PARCELS IS FREDERICK ROBIE, JR. MARITAL TRUST BY DEED DATED MARCH 6, 2019 AND RECORDED AT THE CUMBERLAND COUNTY REGISTRY OF DEEDS (CCRD) IN

24, LOT 8 ON THE AND IS LOCATED IN

- 00 SQ.FT 00 SQ.FT.
- EET*
- FEET: LOCAL ST. EET: ARTERIAL ST. -eet

ON FIELD WORK MEANS AND

- METRY & LIDAR RCEL HEREON IS
- WAS LOCATED
- UMBERLAND DATED JULY 2000
- BY BH2M ON JULY OWARD & 300K 202, PAGE 2. ICCORMACK BY
- (212, PAGE 234. _ CONDITIONS ST THEREOF.
- TH ALL CONTRACT WORK MAY BE DISCREPANCIES IENCEMENT OF
- "EXISTING" WHICH
- ER'S ERWISE
- RIOR TO ALL BE REPORTED
- N PUBLIC STRUCTION.
- TION TO PROTECT RING ITION AND AS
- CTION.
- ORDANCE WITH F LAND AND , OCTOBER 2016 POSSESS A COPY
- REON ARE BASED SY UTILITY OMPLETE. THE RE THAN THIRTY FY HORIZONTAL
- TILITIES ABOUT LITIES IN THE MEMBER UTILITIES WER DISTRICTS
- IENTS OF 23 MRSA WITH THE ANY EXISTING HESE PLANS. IF A OWNER, THE

- 29. BEFORE THE FINAL ACCEPTANCE OF THE PROJECT, THE CONTRACTOR SHALL REMOVE ALL EQUIPMENT AND MATERIALS, REPAIR OR REPLACE PRIVATE OR PUBLIC PROPERTY WHICH MAY HAVE BEEN DAMAGED OR DESTROYED DURING CONSTRUCTION. CLEAN THE AREAS WITHIN AND ADJACENT TO THE PROJECT WHICH HAVE BEEN OBSTRUCTED BY HIS/HER OPERATIONS, AND LEAVE THE PROJECT AREA NEAT AND PRESENTABLE.
- 30. ALL GRAVITY CONDUIT PIPES SHALL BE INSTALLED USING A PIPE LASER AND TARGET SYSTEM THROUGH THE PIPE. ON PIPE RUNS 50 FEET OR LESS, THE THE CONTRACTOR SHALL REQUEST ENGINEER'S APPROVAL TO USE A GROUND LASER.
- 31. SIDESLOPES SHALL NOT BE STEEPER THAN 3:1 (H:V) EXCEPT AS OTHERWISE IDENTIFIED ON THIS PLAN. ALL SIDESLOPES STEEPER THAN 3:1 (H: V) SHALL BE LINED WITH EROSION CONTROL BI ANKET
- 32. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING FLOW THROUGH THE EXISTING CLOSED STORM DRAINAGE SYSTEM DURING CONSTRUCTION AND SHALL SUBMIT A WORK PLAN FOR APPROVAL BY THE DESIGN ENGINEER.
- 33. BOUNDARY INFORMATION SHOWN HEREON IS BASED UPON LIDAR DATA AVAILABLE FROM THE TOWN OF XXXXX AND AS DEPICTED IN PLAN REFERENCE 7A. THE TOPOGRAPHICAL INFORMATION SHOWN HEREON IS SOLELY BASED UPON LIDAR TOPOGRAPHICAL INFORMATION PROVIDED BY THE OWNER. SEBAGO TECHNICS, INC. MAKES NO REPRESENTATION AS TO THE ACCURACY OF THIS INFORMATION, AND THROUGH DIRECTION OF THE OWNER, HAS RELIED UPON THIS INFORMATION FOR THE DESIGN.

UTILITY DEMOLITION NOTES

- 1. PROTECT EXISTING BOUNDARY LINE MONUMENTATION. IF DISTURBED, EXISTING MONUMENTATION TO BE RESET BY A PROFESSIONAL LAND SURVEYOR.
- 2. DEMOLITION OF UTILITIES REQUIRING TREE REMOVAL SHALL BE COORDINATED WITH THE OWNER AND IN ACCORDANCE WITH PROJECT PLANS.
- 3. UTILITY DEMOLITION SHALL BE COMPLETED IN COORDINATION WITH NEW INFRASTRUCTURE. CONTRACTOR SHALL ENSURE EXISTING SURFACE DRAINAGE IS MAINTAINED DURING CONSTRUCTION
- 4. EXISTING SEWER AND STORM DRAINAGE INFRASTRUCTURE TO REMAIN ACTIVE DURING CONSTRUCTION AND UPON COMPLETION OF PROJECT. DEMOLITION/CONSTRUCTION ACTIVITIES SHALL NOT INTERFERE OR IMPEDE EXISTING FLOWS. CONTRACTOR SHALL PROVIDE BYPASS PUMPING AS REQUIRED DURING SEWER AND STORM DEMOLITION AND NEW CONSTRUCTION. DAMAGE TO EXISTING SEWER INFRASTRUCTURE SHALL BE REPAIRED BY CONTRACTOR AT THEIR EXPENSE
- DEMOLITION SHOWN IS FOR MAJOR SITE ELEMENTS TO BE DEMOLISHED. OTHER MINOR DEMOLITION MAY BE REQUIRED AS PART OF CONSTRUCTION AND SHALL BE CONSIDERED INCIDENTAL TO THE COST OF CONSTRUCTION. COORDINATE ALL DEMOLITION WORK WITH SITE AND BUILDING DRAWINGS.
- PRIOR TO ANY DEMOLITION, THE CONTRACTOR SHALL SUBMIT A SEQUENCE OF DEMOLITION PLANS TO THE OWNER. THIS PLAN SHALL DEPICT LOCATIONS OF PROPOSED TERMINATIONS AND ANY TEMPORARY SERVICES THAT WILL BE NEEDED.
- 7. CONTRACTOR REQUIRED TO CONFIRM/MAINTAIN BENCHMARKS. IF IMPACTED CONTRACTOR IS RESPONSIBLE FOR NOTIFICATION/RELOCATION AND COORDINATION WITH PROJECT TEAM.

GRADING & EROSION NOTES

- SIDESLOPES SHALL NOT BE STEEPER THAN 3:1 (H:V) EXCEPT AS OTHERWISE IDENTIFIED ON THIS PLAN. ALL SIDESLOPES STEEPER THAN 3:1 (H: V) SHALL BE LINED WITH EROSION CONTROL BLANKET, OR ADDITIONAL MEASURES AS INDICATED.
- 2. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH MAINE EROSION AND SEDIMENT CONTROL BMPS" MANUAL PUBLISHED BY BUREAU OF LAND AND WATER OUALITY MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION, LATEST EDITION. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO POSSESS A COPY OF THE EROSION CONTROL PLAN AT ALL TIMES.
- 3 ALL AREAS DISTURBED DURING CONSTRUCTION AND NOT RESTORED WITH IMPERVIOUS SURFACES (BUILDINGS, PAVEMENTS, WALKS, ETC.) SHALL RECEIVE LOAM AND SEED PER DETAIL. 4. SEE UTILITY DRAWINGS FOR PIPE AND STRUCTURE DATA TABLES.
- CONSTRUCTION PLAN
- 1. PROVIDE EROSION CONTROL MEASURES PRIOR TO SITE DISTURBANCE.
- 2. WETLANDS, ASSOCIATED SETBACKS AND STREAM SETBACKS TO BE STAKED BY OWNER PRIOR TO SITE DISTURBANCE.
- 3. BEFORE TREE CLEARING, REFER TO PLANS FOR WOODED BUFFER LOCATIONS. TREES SHALL NOT BE CLEARED WITHIN DESIGNATED WOODED BUFFER AREAS.
- 4. GRADING AND CLEARING LIMITS SHALL NOT ENCROACH ON ADJACENT PROPERTIES UNLESS NOTED OTHERWISE ON THE PLANS.
- 5. OPEN AREAS SHALL BE LIMITED TO AREAS BEING WORKED IN. THE AREA STRIPPED OF EXISTING VEGETATION AT ANY GIVEN TIME SHALL BE MINIMIZED AND BE PHASED WHERE PRACTICAL SO THAT AREAS ARE REVEGETATED AND PERMANENTLY STABILIZED REFORE ADDITIONAL AREAS ARE STRIPPED OF EXISTING VEGETATION. CONSTRUCTION BY USE OF RIPRAP, SEED, MULCH, OR OTHER GROUND COVER WITHIN ONE WEEK FROM THE TIME IT WAS ACTIVELY WORKED. SURFACES SHALL BE STABILIZED PRIOR TO DIRECTING STORMWATER RUNOFF TOWARD STORMWATER BMPS. PLEASE REFER TO DRAINAGE PLANS FOR WATERSHED AREAS.

UTILITY NOTES

- 1. UTILITY INFORMATION DEPICTED HEREON IS COMPILED USING PHYSICAL EVIDENCE LOCATED IN THE FIELD. UTILITIES DEPICTED HEREON MAY NOT NECESSARILY REPRESENT ALL EXISTING UTILITIES. CONTRACTORS AND/OR DESIGNERS NEED TO CONTACT DIG-SAFE SYSTEMS, INC. (1-888-DIG-SAFE) AND FIELD VERIFY EXISTING UTILITIES PRIOR TO CONSTRUCTION AND/OR EXCAVATION. PROTECT EXISTING ONSITE SEWER PIPE AND ADJUST MANHOLE RIMS TO GRADE WHERE APPLICABLE.
- 2. ALL GRAVITY CONDUIT PIPES SHALL BE INSTALLED USING A PIPE LASER AND TARGET SYSTEM THROUGH THE PIPE. ON PIPE RUNS 50 FEET OR LESS, THE CONTRACTOR SHALL REQUEST ENGINEER'S APPROVAL TO USE OR NOT USE A GROUND LASER.
- 3. MAINTAIN MINIMUM 5'-6" OF COVER ABOVE TOP OF WATER SERVICE PIPE. 4. MAINTAIN MINIMUM 10 FEET HORIZONTAL SEPARATION BETWEEN WATER SERVICES AND OTHER
- OTHER UTILITIES. 5. LOWER OR RAISE WATER SERVICES AS REQUIRED TO MAINTAIN MINIMUM 12 INCH VERTICAL SEPARATION FROM OTHER UTILITIES. WATER SERVICES CROSSING SEWERS SHALL BE PROVIDE 12 INCH MINIMUM SEPARATION BETWEEN THE BOTTOM OF WATER LINE AND TOP OF SEWER UNLESS
- NOTED OTHERWISE ON THE PLANS. 6. PIPE:
- SEWER PIPE SHALL BE SDR 35 PVC OR APPROVED EQUAL. ٠ FORCEMAIN PIPE SHALL BE DR-11 HDPE OR APPROVED EQUAL STORMDRAIN SHALL BE ADS N-12 DUAL WALL HDPE PIPE WITH SMOOTH-WALLED INTERIOR OR APPROVED EQUAL UNLESS NOTED OTHERWISE ON THE UTILITY PLANS.
- SPECIFICATIONS. MAIN WATER SERVICE PIPE SHALL BE DUCTILE IRON, CLASS 52 PUSH-ON PIPE MEETING THE REQUIREMENTS OF AWWA/ANSI C-111/A21.11 (LATEST REVISION). PIPE SHALL BE CEMENT-LINED AWWA/ANSI C104/A21.4 WITH LINING TWICE THE THICKNESS SPECIFIED. AND
- SERVICE BENDS.
- 7. COORDINATE FOUNDATION UNDERDRAIN LOCATIONS WITH ARCHITECTURAL AND STRUCTURAL DRAWINGS.
- 8. COORDINATE GREASE INTERCEPTOR LOCATIONS WITH ARCHITECTURAL & PLUMBING DRAWINGS.
- 9. COORDINATE UTILITY INVERTS AT BUILDING WITH ARCHITECTURAL, STRUCTURAL AND PLUMBING DRAWINGS.
- 10. COORDINATE LOCATION OF SEWER, WATER, GAS, FOUNDATION DRAINS AND ROOF DRAIN INVERTS AT THE BUILDING WITH ARCHITECTURAL DRAWINGS
- 11. WATER SERVICE ENTRANCE DESIGNS TO INCLUDE METERS AND BACKFLOW PREVENTERS TO MEET ALL STANDARDS AND REQUIREMENTS OF THE PORTLAND WATER DISTRICT.
- 12. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY GRADE CHANGES THAT WILL IMPACT STORM DRAINAGE INFRASTRUCTURE OR OTHER UTILITIES.
- 13. UTILITIES WITHIN 5 FEET FROM FACE OF BUILDING ARE COORDINATED ON RELEVANT M.E.P. DRAWINGS. CONTRACTOR SHALL COORDINATE INVERTS, CONNECTIONS AND MATERIALS WITH ALL DRAWINGS
- 14. CONTRACTOR SHALL FURNISH AND INSTALL TRENCHING, MATERIALS AND BACKFILL FOR ALL UTILITIES. ELECTRICAL AND TELECOM/DATA PROVIDERS WILL PULL PRIMARY SERVICE TO TRANSFORMER AND PANEL. CONTRACTOR RESPONSIBLE FOR TIMING AND COORDINATION WITH UTILITIES AND DRAWINGS. COORDINATE WITH ELECTRICAL DRAWINGS FOR CONDUIT SCHEDULE, TYPE AND SIZES.
- 15. COORDINATE ALL WATER RELATED WORK WITH PORTLAND WATER DISTRICT.
- 16. UTILITY CONTACTS: ELECTRIC:
- CENTRAL MAINE POWER (CMP) VAN A. HOBGOOD, DISTRIBUTION ENGINEERING (207) 490-3075 WATER: PORTLAND WATER DISTRICT ROBERT BARTELS, ENGINEER (207) 774-5961 FAIRPOINT: RICHARD JENSEN (207) 797-1015

LANDSCAPE NOTES

- PLANT QUANTITIES SHOWN ON PLANT LISTS ARE FOR CONVENIENCE TO THE CONTRACTOR ONLY. THE CONTRACTOR IS RESPONSIBLE FOR ALL PLANT MATERIAL INSTALLATION AS SHOWN ON PLANS.
- 2. SIZE AND GRADING STANDARDS OF PLANT MATERIALS SHALL CONFORM TO THE LATEST EDITION OF "U.S.A. STANDARD FOR NURSERY STOCK," BY THE AMERICAN ASSOCIATION OF NURSERYMEN,
- 3. ALL PLANT MATERIAL SHALL BE FREE FROM INSECTS AND DISEASE. 4. ALL PLANTING SHALL BE DONE IN ACCORDANCE WITH ACCEPTABLE HORTICULTURAL PRACTICES. THIS IS TO INCLUDE PROPER PLANTING MIX, PLANT BED AND TREE PIT PREPARATION, PRUNING,
- STAKING OR GUYING, WRAPPING, SPRAYING, FERTILIZATION, PLANTING AND ADEQUATE MAINTENANCE UNTIL ACCEPTANCE BY THE OWNER. 5. PLANT MATERIAL SHALL BE GUARANTEED FOR A PERIOD OF ONE YEAR BY THE CONTRACTOR
- AND A PERIOD OF TWO YEARS THEREAFTER BY THE OWNER FROM DATE OF INSTALLATION. DURING THE ONE YEAR GUARANTEE PERIOD, DEAD PLANT MATERIAL SHALL BE REPLACED AT NO COST TO THE OWNER. AT THE END OF THE ONE YEAR PERIOD, THE CONTRACTOR SHALL OBTAIN FINAL ACCEPTANCE FROM THE OWNER.
- 6. ALL GRASS, OTHER VEGETATION AND DEBRIS SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO PLANTING.
- 7. EXISTING TREES TO BE PRESERVED WILL BE PROTECTED DURING CONSTRUCTION AND SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR.
- 8. THE LANDSCAPE CONTRACTOR IS ADVISED OF THE PRESENCE OF THE UNDERGROUND UTILITIES AND SHALL VERIFY THE EXISTENCE AND LOCATION OF SAME BEFORE COMMENCING AND DIGGING OPERATIONS. THE LANDSCAPE CONTRACTOR SHALL REPLACE OR REPAIR UTILITIES, PAVING, WALKS, CURBING, ETC. DAMAGED IN PERFORMANCE OF THIS JOB AT NO ADDITIONAL COST TO THE OWNER.
- 9. ALL SHRUB BEDS SHALL BE MULCHED WITH 3" CLEAN SHREDDED DARK BROWN BARK MULCH. 10. THE CONTRACTOR SHALL PROVIDE 4" LOAM FOR ALL AREAS TO BE SODDED OR SEEDED. PLANTING AREAS SHALL RECEIVE 12" ROLLED THICKNESS OF LOAM. THE LANDSCAPE CONTRACTOR SHALL COORDINATE SUBGRADE PREPARATION WITH THE GENERAL CONTRACTOR PRIOR TO PLACING LOAM.
- 11. ANY DEVIATION FROM THE LANDSCAPE PLAN, INCLUDING PLANT LOCATION, SELECTION, SIZE, QUANTITY OR CONDITION SHALL BE REVIEWED AND APPROVED BY THE OWNER AND LANDSCAPE ARCHITECT (AND MUNICIPAL AUTHORITY, IF APPLICABLE) PRIOR TO INSTALLATION ON SITE.
- 12. WHERE INDICATED ON PLAN, PLANTING SOIL MIXTURE FOR PERENNIAL AND ANNUAL FLOWER BED AREAS SHALL CONSIST OF FOUR PARTS TOPSOIL, TWO PARTS SPHAGNUM PEAT MOSS. AND ONE PART HORTICULTURAL PERLITE BY VOLUME. PEAT MOSS MAY BE SUBSTITUTED WITH WELL-ROTTED OR DEHYDRATED MANURE OR COMPOST. ROTOTILL BEDS TO A DEPTH OF 8 INCHES.

MAP 27 LOT 20 MAP 25 LOT 8 MAP 24 LOT 20 & 19

COATED TWICE WITH A BITUMINOUS SEAL COATING. PROVIDE THRUST BLOCKS AT ALL WATER

WATER PIPE AND FITTINGS SHALL CONFORM TO PORTLAND WATER DISTRICT WATER PIPING

UTILITIES. MAINTAIN MINIMUM 18 INCHES VERTICAL SEPARATION BETWEEN WATER SERVICES AND

TYPICAL ABBREVIATIONS

BITUMINOUS CONCRETE CURB

ABOVE FINISH GRADE

BOTTOM OF CURB

BOTTOM OF WALL

CATCH BASIN

CONCRETE

DIAMETER

FACH WAY

ELEVATION

FOOTING

HEIGHT

INVERT

RADIUS

I INFAR FFFT

ON CENTER

RIGHT OF WAY

SQUARE FEET

STORM DRAIN

TOP OF CURB

TOP OF WALL

VERIFY IN FIELD

TYPICAL

SANITARY SEWER

SLOPED GRANITE CURB

VERTICAL GRANITE CURB

SCHEDULE

FIN. GR. FINISH GRADE

CONTINUOUS

DUCTILE IRON

DRAIN MANHOLE

HOT MIX ASPHALT

POLYVINYL CHLORIDE

PORTLAND WATER DISTRICT

SLIPFORM CONCRETE SLOPED CURB

SLIPFORM CONCRETE VERTICAL CURB

SALVAGED SLOPED GRANITE CURB

SALVAGED VERTICAL GRANITE CURB

SEWER MANHOLE SPECS SPECIFICATIONS

비끼

0 Z Z

SUBDIVISIO

TREET

DESIGNED

DRAWN

CHECKED

DATE

SCALE

PROJECT

SHEET 2 OF 29

LEGEND

ళ

()

S, S

S

ш

JBP

STI SMF

05/31/2022

NTS

21483

FINISH FLOOR ELEVATION

HIGH DENSITY POLYETHYLENE

BITUMINOUS

BUILDING

ACRE

APPROX. APPROXIMATELY

AC

AFG

BCC

BLDG

CONC

CONT

DIA

DMH

E.W.

ELEV

FFE

FTG

HDPE

HGT

HMA

INV

OC

PVC

PWD

R.O.W.

S.F.

SCH

SCSC

SCVC

SGC

SMH SS

SSGC

SVGC

ΤW

TYP

VGC


VIF


SD

BW

СВ

BIT





SCALE


PROJECT

SHEET 3 OF29

1" = 200'


21483

7690/188



NRA UR = 45.3 ACRES X 43,560 SF/AC X 0.65/10,000 SF/UNIT = 128.3 UNITS AREA IN UBRAN RESIDENTIAL EXTENSION ZONE = 85.8 ACRES NRE URE = 85.8 ACRES X 43,560 SF/AC = 3,737,448 SF - 15% ROW (560,617 SF) - SLOPES > 20% (151,570 SF) - WETLANDS (895,267 SF) - STREAM AREA (11,212 SF) = NRA = 2,118,782 SF /20,000 SF/UNIT = 105.9 UNITS

131.1 ACRES X 43,560 SF/AC X 0.65/5,000 SF/UNIT = 742 UNITS




AS IT WILL BE PRIVATE HYDRANTS, UNLESS THE TOWN ACCEPTS THE STREETS.

MAP 27 LOT 20

MAP 25 LOT 8

MAP 24 LOT 20 & 19



 \mathbf{O}

S

S

R

Ш

Ż

ш

JBP

STI

SMF

05/31/2022

1" = 200'

21483

₩>

DESIGNED

DRAWN


CHECKED

DATE

SCALE

PROJECT

SHEET 4 OF29




CTION	DISTANCE
30'16" E	39.90'
30'16" W	39.90'
17'16" W	157.94'
39'14" W	9.70'
19'12" W	14.80'
14'20" E	45.56'
07'42" E	5.81'
07'42" E	23.94'
15'24" E	28.01'
15'24" E	12.55'
244'36" E	38.86'
41'56" E	64.06'
41'56" W	54.32'
44'36" W	38.86'
15'24" W	3.61'
13'49" W	3.10'
39'14" W	1.25'

EASEMENT LIN		IE TABLE
LINE DIRECTION		DISTANCE
EL35 S 66°33'30" W		59.67'
EL36	S 23°26'30" E	75.00'
EL37	N 66°33'30" E	60.18'
EL38	S 21°29'56" E	123.84'
EL40	N 66°26'09" E	45.01'
EL41	N 22°24'56" W	217.02'
EL42	S 66°44'36" W	45.00'
EL43	S 23°15'24" E	225.76'
EL44	S 66°47'58" W	45.00'
EL45	N 66°44'36" E	45.00'
EL46	S 26°03'44" E	126.32'
EL47	N 15°25'18" W	172.00'
EL48	N 74°34'42" E	150.00'
EL49	S 15°25'18" E	172.00'
EL50	S 74°34'42" W	150.00'
EI 51	S 45°30'50" E	273 86'

LINE DIRECTION DISTANCE EL52 N 44°29'10" E 210.01' EL53 N 49°50'25" W 359.94' EL54 S 51°42'51" W 154.08' EL55 S 45°30'50" E 104.44' EL56 S 44°29'10" W 30.00' EL57 N 45°30'50" W 25.00' EL58 N 44°29'10" E 10.00' EL59 S 45°30'50" E 30.00'	EASEMENT LINE TABLE					
EL53 N 49°50'25" W 359.94' EL54 S 51°42'51" W 154.08' EL55 S 45°30'50" E 104.44' EL56 S 44°29'10" W 30.00' EL57 N 45°30'50" E 10.00' EL58 N 44°29'10" E 10.00' EL59 S 45°30'50" E 30.00'	LINE	DIRECTION	DISTANCE			
EL54 S 51°42'51" W 154.08' EL55 S 45°30'50" E 104.44' EL56 S 44°29'10" W 30.00' EL57 N 45°30'50" W 25.00' EL58 N 44°29'10" E 10.00' EL59 S 45°30'50" E 30.00'	EL52	N 44°29'10" E	210.01'			
EL55 S 45°30'50" E 104.44' EL56 S 44°29'10" W 30.00' EL57 N 45°30'50" W 25.00' EL58 N 44°29'10" E 10.00' EL59 S 45°30'50" E 30.00'	EL53	N 49°50'25" W	359.94'			
EL56 S 44°29'10" W 30.00' EL57 N 45°30'50" W 25.00' EL58 N 44°29'10" E 10.00' EL59 S 45°30'50" E 30.00'	EL54	S 51°42'51" W	154.08'			
EL57 N 45°30'50" W 25.00' EL58 N 44°29'10" E 10.00' EL59 S 45°30'50" E 30.00'	EL55	S 45°30'50" E	104.44'			
EL58 N 44°29'10" E 10.00' EL59 S 45°30'50" E 30.00'	EL56	S 44°29'10" W	30.00'			
EL59 S 45°30'50" E 30.00'	EL57	N 45°30'50" W	25.00'			
	EL58	N 44°29'10" E	10.00'			
EL60 S 44°29'10" W 10.00'	EL59	S 45°30'50" E	30.00'			
	EL60	S 44°29'10" W	10.00'			
EL61 S 45°30'50" E 133.39'	EL61	S 45°30'50" E	133.39'			
EL62 N 70°17'00" E 180.16'	EL62	N 70°17'00" E	180.16'			
EL63 N 70°17'00" E 181.09'	EL63	N 70°17'00" E	181.09'			
EL64 S 45°30'50" E 83.95'	EL64	S 45°30'50" E	83.95'			

CURVE	LENGTH	RADIUS	CRE
EC1	44.82'	40.00'	S
EC2	11.21'	10.00'	S

CURVE	RADIUS	LENGTH	C
CL1	350.00'	103.43'	
CL2	1103.00'	500.89'	
CL3	300.00'	121.01'	
CL4	300.00'	121.10'	
CL5	120.00'	192.44'	
CL6	230.00'	83.14'	
CL7	400.00'	186.52'	





SANITARY SEWER STRUCTURE DATA					
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.	
SMH-14	220.77	206.90 (S-15)	206.80 (S-14)	48"	
SMH-15	221.53	207.40 (S-16)	207.30 (S-15)	48"	

SANI	E DATA		
NAME	SIZE	LENGTH	SLOPE
S-15	8"	87'	0.46%
S-16	8"	185'	0.49%
S-157	10"	212'	0.48%

STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.
CB-9	220.46	212.50 (SD-17)	212.40 (SD-16)	48"
CB-10	220.79	212.10 (SD-16)	212.00 (SD-15)	60"
CB-11	220.46	213.00 (SD-77) 216.90 (SD-18)	212.70 (SD-17)	48"
CB-69	221.18	217.30 (SD-62)	217.20 (SD-63)	48"
DMH-5	221.70	217.00 (SD-63)	214.75 (SD-77)	48"

STORM DRAIN PIPE			DATA
NAME	SIZE	LENGTH	SLOPE
SD-15	15"	23'	0.89%
SD-16	15"	53'	0.57%
SD-17	15"	17'	1.15%
SD-18	12"	6'	8.53%
SD-62	15"	271'	0.55%
SD-63	15"	33'	0.61%
SD-73	15"	176'	0.85%
SD-77	15"	216'	0.81%






SANITARY SEWER STRUCTURE DATA				
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.
SMH-16	222.87	208.40 (S-17)	208.30 (S-16)	48"
SMH-17	222.11	208.90 (S-18)	208.80 (S-17)	48"
SMH-18	220.65	209.70 (S-19)	209.60 (S-18)	48"


SANITARY SEWER PIPE DATA						
NAME	SIZE	LENGTH	SLOPE			
S-16	8"	185'	0.49%			
S-17	8"	81'	0.49%			
S-18	8"	145'	0.48%			
S-19	8"	225'	0.49%			

STORM DRAIN STRUCTURE DATA					
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.	
CB-12	220.37	216.40 (SD-75)	216.30 (SD-32)	48"	
CB-13	220.37	216.10 (SD-32)	216.00 (SD-35)	48"	

STORM DRAIN PIPE DATA					
NAME	SIZE	LENGTH	SLOPE		
SD-32	12"	17'	1.17%		
SD-34	12"	106'	0.47%		
SD-47	18"	177'	0.51%		








SANITARY	SANITARY SEWER STRUCTURE DATA					
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.		

SANITARY SEWER PIPE DATA					
NAME	SIZE	LENGTH	SLOPE		


STORM DRAIN STRUCTURE DATA						
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.		
CB-14	218.88	215.00 (SD-33)	214.90 (SD-34)	48"		
CB-15	218.88		215.15 (SD-33)	48"		
CB-50	219.78	214.40 (SD-34) 215.50 (SD-35)	214.30 (SD-46)	48"		

STORM DRAIN PIPE DATA


NAME	SIZE	LENGTH	SLOPE
SD-33	12"	17'	0.86%
SD-34	12"	106'	0.47%
SD-46	15"	301'	0.60%
SD-48	18"	76'	1.31%



PROFILE VIEW SCALE: HORZ. 1" = 20' VERT. 1" = 4'




SHAWN M. FRANK, PE 6396	С. С
	C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION TO TOWN REV: BY: DATE: STATUS: THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC.
	Tel. 207-200-2100
	LE ROAD A - STA 108+00 - 112+00 ET SUBDIVISION IT SUBDIVISION RECORD OWNER: FREDERICK ROBIE, JR. C/O BRUCE ROBIE JUITE 1030 HOLDEN, ME
	PLAN & PROFILE ROAD A - STA 1 of: ROBIE STREET SUBDIVISION ROBIE STREET GORHAM, MAINE FOR: FOR: KV ENTERPRISES, LLC 91 AUBURN STREET, SUITE 1030 PORTLAND, MAINE
	DESIGNEDJBPDRAWNSTICHECKEDSMFDATE05/31/2022SCALE1" = 20'PROJECT21483SHEET 8 OF29



VERT. 1" = 4'

SHAWN M. FRANK, PE 6396	ССССССССССССССССССССССССССССССССССССС
	C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION REV: BY: DATE: STATUS: THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LABILITY TO SEBAGO TECHNICS. INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LABILITY TO SEBAGO TECHNICS. INC.
	South Portland, ME 04106 Tel. 207-200-2100
	ROAD B - STA 200+00 - 204+50 SUBDIVISION RECORD OWNER: FREDERICK ROBIE, JR. C/O BRUCE ROBIE, JR. C/O BRUCE ROBIE 1030 HOLDEN, ME
	OFILE REET PRIS
	PLAN & PR of: ROBIE STI ROBIE STI ROBIE STREET GORHAM, MAINE FOR: KV ENTER 91 AUBURN STRE PORTLAND, MAIN
	NVAL </td



TA DIAM. 48" 48" 48"	210	`	-2.05%		PVC: 207+39.92 ELEV: 202.02
	200		SD-11	SD-10 SD	SD-8
M. "		SMH-12 STA:204+80.30 OFF:4.60'R RIM:207.24 INV. IN:198.90 (S-13) INV. OUT:198.80 (S-12) DMH-4 STA:204+93.26 OFF:10.61'R RIM:206.85 INV. IN:202.60 (SD-12) INV. OUT:202.50 (SD-11)	SMH-11 STA:205+46.14 OFF:4.73'R RIM:205.89 INV. IN:197.50 (S-12) INV. OUT:197.40 (S-11) DMH-3 STA:205+55.65 OFF:10.52'R RIM:205.58 INV. IN:201.30 (SD-11) INV. OUT:201.20 (SD-10)	CB-5 STA:206+29.95 OFF:-10.71'L RIM:204.06 INV. OUT:200.40 (SD-9) CB-6 STA:206+29.83 OFF:10.71'R RIM:204.06 INV. IN:199.80 (SD-10) INV. IN:200.20 (SD-9) INV. OUT:199.30 (SD-8)	SMH-10 STA:207+51.05 OFF:5.7 RIM:201.69 INV. IN:193.35 (S-11) INV. OUT:193.25 (S-10)
<u>DATUM EL</u> 180.00	<u>EV.</u> 8 ³⁰² 204		205+00	206+00 207+00	200.3 201.81

SANITARY SEWER STRUCTURE DATA						
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.		
SMH-9	198.78	190.45 (S-10)	190.35 (S-9)	48"		
SMH-10	201.69	193.35 (S-11)	193.25 (S-10)	48"		
SMH-12	207.24	198.90 (S-13)	198.80 (S-12)	48"		

SANITARY SEWER PIPE DATA


NAME	SIZE	LENGTH	SLOPE
S-9	8"	141'	2.52%
S-10	8"	120'	2.34%
S-12	8"	63'	2.08%
S-13	8"	214'	2.61%


STORM DRAIN STRUCTURE DATA						
STRUCTURE	RIM	RIM INV. IN INV. OUT: DI				
CB-3	198.47		194.80 (SD-7)	48"		
CB-4	198.47	193.60 (SD-8) 194.60 (SD-7)	193.50 (SD-6)	48"		
CB-5	204.06		200.40 (SD-9)	48"		
CB-6	204.06	199.80 (SD-10) 200.20 (SD-9)	199.30 (SD-8)	48"		
DMH-4	206.85	202.60 (SD-12)	202.50 (SD-11)	48"		


STORM DRAIN PIPE DATA


NAME	SIZE	LENGTH	SLOPE
SD-7	12"	17'	1.17%
SD-8	24"	247'	2.31%
SD-9	12"	17'	1.15%
SD-11	18"	60'	1.99%
SD-12	18"	158'	2.21%

PROFILE VIEW SCALE: HORZ. 1" = 20' VERT. 1" = 4'









SANITARY SEWER STRUCTURE DATA


STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.
SMH-6	189.83	181.50 (S-7)	181.40 (S-6)	48"
SMH-7	192.31	184.00 (S-8)	183.90 (S-7)	48"
SMH-8	195.14	186.80 (S-9)	186.70 (S-8)	48"


SANITARY SEWER PIPE DATA						
NAME	SIZE	LENGTH	SLOPE			
S-7	8"	192'	1.25%			
S-8	8"	115'	2.34%			
S-9	8"	141'	2.52%			

STORM DRAIN STRUCTURE DATA						
STRUCTURE RIM INV. IN INV. OUT: D						
CB-1	189.73	185.55 (SD-79)	185.45 (SD-4)	48"		
CB-2	189.70	184.35 (SD-51) 185.30 (SD-4)	184.25 (SD-3)	60"		
CB-37	189.79	184.10 (SD-3)	184.00 (SD-50)	60"		
CB-44	191.95 187.10 (SD-6) 188.10 (SD-39) 188.30 (SD-42) 186.60 (SD-51) 60"		60"			
CB-45	191.96		188.30 (SD-39)	48"		

STORM DRAIN PIPE DATA					
NAME SIZE LENGTH SLOPE					
SD 3	20"	າງ	0.70%		

SD-3	30"	22'	0.70%
SD-4	12"	17'	0.87%
SD-6	24"	261'	2.45%
SD-39	12"	17'	1.18%
SD-42	12"	5'	3.91%
SD-50	30"	23'	2.63%
SD-51	30"	152'	1.48%






SANITARY SEWER STRUCTURE DATA					
STRUCTURE RIM INV. IN INV. OUT: DIAM.					
SMH-1	186.99	177.40 (S-2)	177.30 (S-1)	48"	
SMH-2	186.79	178.00 (S-3)	177.90 (S-2)	48"	
SMH-3	187.38	178.50 (S-4)	178.40 (S-3)	48"	


SANITARY SEWER PIPE DATA

NAME	SIZE	LENGTH	SLOPE
S-1	8"	52'	0.58%
S-2	8"	104'	0.48%
S-3	8"	80'	0.50%
S-4	8"	165'	0.49%

STORM DRAIN PIPE DATA						
NAME	SIZE	LENGTH	SLOPE			
SD-44	36"	47'	1.60%			








SANITARY SEWER STRUCTURE DATA					
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.	
SMH-4	188.59	179.40 (S-5)	179.30 (S-4)	48"	
SMH-5	189.27	180.00 (S-6)	179.90 (S-5)	48"	
SMH-6	189.83	181.50 (S-7)	181.40 (S-6)	48"	
SMH-7	192.31	184.00 (S-8)	183.90 (S-7)	48"	


SANITARY SEWER PIPE DATA					
NAME	SIZE	LENGTH	SLOPE		
S-4	8"	165'	0.49%		
S-5	8"	96'	0.52%		
S-6	8"	259'	0.54%		
S-7	8"	192'	1.25%		
S-8	8"	115'	2.34%		


STORM DRAIN STRUCTURE DATA						
STRUCTURE RIM INV. IN INV. OUT: DIAM.						
CB-1	189.73	185.55 (SD-79)	185.45 (SD-4)	48"		
CB-2	189.70	184.35 (SD-51) 185.30 (SD-4)	184.25 (SD-3)	60"		
CB-37	189.79	184.10 (SD-3)	184.00 (SD-50)	60"		

STORM DRAIN PIPE DATA					
NAME	SIZE	LENGTH	SLOPE		
SD-3	30"	22'	0.70%		
SD-4	12"	17'	0.87%		
SD-41	36"	51'	1.17%		
SD-50	30"	23'	2.63%		
SD-51	30"	152'	1.48%		




SHAWN M. FRANK, PE 6396	S S S S S S S S S S S S S S					
	C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION TO TOWN THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATION AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC. ANY ALTERATION					
	Tel. 207-200-2100					
	PLAN & PROFILE OF STA 500+00 - 504+50OF: <tr< td=""></tr<>					






	PLAN VIEW - ROAD SCALE: 1" = 20"		MATCH LINE STA 497+71 SEE SHEET 16	GRAPHIC SCALE (IN FEET) (IN FEET) 1 INCH = 20 FT.	Image: Signal state in the
				00	Image: Second State Sta
Q SD-66	0.70%			90	ROFILE ROAD D STA 493+71 - 497+71 ROFILE ROAD D STA 493+71 - 497+71 TREET SUBDIVISION E RECORD OWNER: FREDERICK ROBIE, IR: C/O BRUCE ROBIE, IR: IR: SUITE 1030
5+00	CB-75 STA:496+49.18 OFF:-10 RIM:189.14 INV. IN:182.30 (SD-76) INV. IN:182.50 (SD-66) INV. OUT:182.40 (SD-70 496+00 A96+00 PROFILE VIEW - RC SCALE: HORZ. 1" = 20' VERT. 1" = 4'	0000 1000 1000 1000 1000 1000 1000 100	1 <u>1 88</u> 80 497+7	⁷⁰ MAP 27 LOT 20 MAP 25 LOT 8 MAP 24 LOT 20 & 19	Handler Handler




PROFILE VIEW - ROAD D SCALE: HORZ. 1" = 20' VERT. 1" = 4'

SHAWN M. FRANK, PE 6396	Construction of the second of
	C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION TO TOWN FEV: BY: DATE: STATUS: THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC.
	TECHNICS.COM TRANSEBAGOTECHNICS.COM 75 John Roberts Rd. Suite 4A South Portland, ME 04106 Tel. 207-200-2100
	PLAN & PROFILE ROAD D STA 497+71 - 500+00 or: ROBIE STREET SUBDIVISION ROBIE STREET GORHAM, MAINE FOR: FOR: FOR: FOR: FOR: FOR: FOR: FOR:
	DESIGNEDJBPDRAWNSTICHECKEDSMFDATE05/31/2022SCALE1" = 20'PROJECT21483SHEET16 OF29

MAP 24 LOT 20 & 19









STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.
CB-68	222.80		218.80 (SD-62)	48"
CB-69	221.18	217.30 (SD-62)	217.20 (SD-63)	48"
DMH-5	221.70	217.00 (SD-63)	214.75 (SD-77)	48"

STORM DRAIN PIPE DATA					
NAME SIZE LENGTH SLOPE					
SD-62	15"	271'	0.55%		
SD-63	15"	33'	0.61%		
SD-77	15"	216'	0.81%		

<u>ROBIE STREET</u> SCALE: H: 1" = 40' V: 1" = 20'





DATE

SCALE


PROJECT


SHEET 1 OF 1


05/31/2022


########

21483










KEY PLAN

·----



STORIN DRAIN FIFE DATA						
NAME	SIZE	LENGTH	SLOPE			
SD-32	12"	17'	1.17%			

	00 02	12		1.17 /0
	SD-33	12"	21'	0.70%
	SD-34	12"	110'	0.45%
	SD-35	12"	57'	0.88%
	SD-46	15"	303'	0.59%
	SD-48	18"	76'	1.31%
	SD-74	12"	17'	0.86%
/	SD-75	12"	25'	0.80%
-				

STORM DRAIN PIPE DATA


STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.
CB-12	220.37	216.40 (SD-75)	216.30 (SD-32)	48"
CB-13	220.37	216.10 (SD-32)	216.00 (SD-35)	48"
CB-14	218.88	215.00 (SD-33)	214.90 (SD-34)	48"
CB-15	218.88		215.15 (SD-33)	48"
CB-50	219.78	214.40 (SD-34) 215.50 (SD-35)	214.30 (SD-46)	48"
CB-83	220.45		216.85 (SD-74)	48"
CB-84	220.45	216.70 (SD-74)	216.60 (SD-75)	48"


SHAWN M. FRANK, PE 6396	ССССССО СССССССССССССССССССССССССССССС
S	C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION TO TOWN REV: BY: DATE: STATUS: THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USERS SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC. ANY ALTERATIONS.
	T E C H N - C MWW.SEBAGOTECHNICS.COM 75 John Roberts Rd. Suite 4A South Portland, ME 04106 Tel. 207-200-2100
	DN <u>RECORD OWNER:</u> FREDERICK ROBIE,JR. C/O BRUCE ROBIE 32 BEECHNUT LANE HOLDEN, ME
	GRADING PLAN 2 of: ROBIE STREET SUBDIVISION ROBIE STREET GORHAM, MAINE FOR: FOR: FOR: FOR: FOR: FOR: FOR: FOR:
	DESIGNEDJBPDRAWNSTICHECKEDSMFDATE05/31/2022SCALE1" = 30'PROJECT21483

SHEET20 OF29



												190 ->	
	LOT 5					LOT 3 						LOT	
200+00			\rightarrow			21	1+00	e e e e e e e e e e e e e e e e e e e					
209+00 			· %	SD-6					192	212+00			
CB-4			LOT 43	GRADE GRASSED S' LOTS TO DIRECT RU SEE DETAIL STONE CHECK DAM				30' EASEMENT		42 DD 188.50 NCBAN EXPANSION EXPANSION ZONE	SD-51		
		- 195 											
	IN STRUC	TURE DA	TA										
RIM 189.73	INV. IN 185.55 (SD-79)	INV. OUT: 185.45 (SD-4)	DIAM. 48"	,		7		,					1
189.70	184.35 (SD-51) 185.30 (SD-4)	184.25 (SD-3)	60"				- 	0		 / \			
198.47 198.47	193.60 (SD-8) 194.60 (SD-7)	194.80 (SD-7) 193.50 (SD-6)	48" 48"	,/)~	'		
204.06		200.40 (SD-9)	48"										
204.06 189.79	199.80 (SD-10) 200.20 (SD-9) 184.10 (SD-3)	199.30 (SD-8) 184.00 (SD-50)	48" 60"								(
191.95	187.10 (SD-6) 188.10 (SD-39) 188.30 (SD-42)	186.60 (SD-51)	60"	1						12 - Q			N.
191.96		188.30 (SD-39)	48"	5	, 		,1			s /		2	
189.28 189.28	180.50 (SD-71) 180.60 (SD-70)	180.50 (SD-71) 180.50 (SD-72)	48" 48"										
190.25	183.38 (SD-50) 180.20 (SD-72)	179.70 (SD-52)	60"										
		-		-									





STORM	DRA	IN STRUC	TURE DA	ΓA
STRUCTURE	RIM	INV. IN	INV. OUT:	DIAM.
DMH-1	180.50	175.50 (SD-2)	175.40 (SD-1)	60"
DMH-2	181.50	176.30 (SD-52)	176.20 (SD-2)	60"
OCS-1	177.75	171.50 (SD-45)	171.00 (SD-38)	48"

NAME	SIZE	LENGTH	SLOPE
SD-1	30"	44'	0.91%
SD-2	30"	109'	0.64%
SD-38	18"	45'	1.10%
SD-45	6"	5'	0.00%
SD-50	30"	26'	2.38%

EROSION CONTROL MEASURES

PRIOR TO THE BEGINNING OF ANY CONSTRUCTION, SEDIMENT BARRIERS (SILT FENCE) WILL BE STAKED/INSTALLED ACROSS THE SLOPE(S), ON THE CONTOUR AT OR JUST BELOW THE LIMITS OF CLEARING OR GRUBBING, AND/OR JUST ABOVE ANY ADJACENT PROPERTY LINE OR WATERCOURSE TO PROTECT AGAINST CONSTRUCTION RELATED EROSION. THE PLACEMENT OF SEDIMENT BARRIERS SHALL BE COMPLETED IN ACCORDANCE WITH GUIDELINES ESTABLISHED IN BEST MANAGEMENT PRACTICES AND IN ACCORDANCE WITH THIS EROSION CONTROL PLAN AND DETAILS IN THIS PLAN SET. THIS NETWORK IS TO BE MAINTAINED BY THE CONTRACTOR UNTIL ALL EXPOSED SLOPES HAVE AT LEAST 90% VIGOROUS PERENNIAL VEGETATIVE COVER TO PREVENT EROSION. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER PERMANENT STABILIZATION IS ATTAINED.

PRIOR TO ANY CLEARING OR GRUBBING, A CONSTRUCTION ENTRANCE/EXIT SHALL BE CONSTRUCTED AT THE INTERSECTION OF THE PROPOSED ENTRANCES AND EXISTING ROADWAY TO AVOID TRACKING OF MUD, DUST AND DEBRIS FROM THE SITE.

PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL PREPARE A DETAILED SCHEDULE AND MARKED UP PLAN INDICATING AREAS AND COMPONENTS OF THE WORK AND KEY DATES SHOWING DATE OF DISTURBANCE AND COMPLETION OF THE WORK. THE CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION MEETING WITH THE MUNICIPAL STAFF. THREE COPIES OF THE SCHEDULE AND MARKED UP PLAN SHALL BE PROVIDED TO THE MUNICIPALITY THREE DAYS PRIOR TO THE SCHEDULED PRE-CONSTRUCTION MEETING. SPECIAL ATTENTION SHALL BE GIVEN TO THE 14 DAY LIMIT OF DISTURBANCE IN THE SCHEDULE ADDRESSING TEMPORARY AND PERMANENT VEGETATION MEASURES.

CONSTRUCTION AND POST-CONSTRUCTION PHASE

AREAS UNDERGOING ACTUAL CONSTRUCTION SHALL ONLY EXPOSE THAT AMOUNT OF MINERAL SOIL NECESSARY FOR PROGRESSIVE AND EFFICIENT CONSTRUCTION. AN AREA CONSIDERED OPEN IS ANY AREA NOT STABILIZED WITH PAVEMENT, VEGETATION, MULCHING, EROSION CONTROL MATS, RIPRAP OR GRAVEL BASE ON A ROAD, SUCH AS ACTIVE EXCAVATION AND ACTIVE GRADING. LIMIT THE EXPOSED AREA TO THOSE AREAS IN WHICH WORK IS ACTIVELY OCCURRING OR CAN BE MULCHED IN THE SAME DAY. OPEN AREAS SHALL BE ANCHORED WITH TEMPORARY EROSION CONTROL AS SHOWN ON THE DESIGN PLANS AND AS DESCRIBED WITHIN THIS EROSION CONTROL PLAN WITHIN SEVEN (7) DAYS OF DISTURBANCE. AREAS LOCATED WITHIN 100 FEET OF STREAMS SHALL BE ANCHORED WITH TEMPORARY EROSION CONTROL WITHIN SEVEN (7) DAYS. REFER TO WINTER EROSION CONTROL NOTES FOR THE TREATMENT OF OPEN AREAS AFTER OCTOBER 1ST OF THE CONSTRUCTION YEAR.

THE CONTRACTOR MUST INSTALL ANY ADDED MEASURES WHICH MAY BE NECESSARY TO CONTROL EROSION/SEDIMENTATION FROM THE SITE DEPENDENT UPON THE ACTUAL SITE AND WEATHER CONDITIONS. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, IN ORDER TO MINIMIZE AREAS WITHOUT EROSION CONTROL PROTECTION.

EROSION CONTROL APPLICATIONS & MEASURES THE PLACEMENT OF EROSION CONTROL MEASURES SHALL BE COMPLETED IN ACCORDANCE WITH GUIDELINES ESTABLISHED IN BEST MANAGEMENT PRACTICES AND IN ACCORDANCE WITH THE EROSION CONTROL PLAN AND DETAILS IN THE PLAN SET.

TEMPORARY MULCHING:

PRE-CONSTRUCTION PHASE

ALL DISTURBED AREAS SHALL BE MULCHED WITH MATERIALS SPECIFIED BELOW PRIOR TO ANY STORM EVENT. ALL DISTURBED AREAS NOT FINAL GRADED WITHIN 14 DAYS SHALL BE MULCHED. DISTURBED AREAS ADJACENT TO NATURAL RESOURCES THAT ARE NOT GRADED WITHIN SEVEN (7) DAYS SHALL BE MULCHED. ALSO, AREAS, WHICH HAVE BEEN TEMPORARILY OR PERMANENTLY SEEDED, SHALL BE MULCHED IMMEDIATELY FOLLOWING SEEDING. EROSION CONTROL BLANKETS ARE RECOMMENDED TO BE USED AT THE BASE OF GRASSED WATERWAYS AND ON SLOPES GREATER THAN 33%. MULCH ANCHORING SHOULD BE USED ON SLOPES GREATER THAN 5% AFTER SEPTEMBER 15TH OF THE CONSTRUCTION YEAR (SEE WINTER EROSION CONTROL NOTES). TYPES OF MULCH:

HAY OR STRAW: SHALL BE APPLIED AT A RATE OF 75 LBS/1,000 S.F. (1.5 TONS PER ACRE).

EROSION CONTROL MIX: SHALL BE PLACED EVENLY AND MUST PROVIDE 100% SOIL COVERAGE. EROSION CONTROL MIX SHALL BE APPLIED SUCH THAT THE THICKNESS ON SLOPES 3:1 OR LESS IS 2 INCHES PLUS 1/2 INCH PER 20 FEET OF SLOPE UP TO 100 FEET. THE THICKNESS ON SLOPES BETWEEN 3:1 AND 2:1 SHALL BE 4 INCHES PLUS 1/2 INCH PER 20 FEET OF SLOPE UP TO 100 FEET. THIS SHALL NOT BE USED ON SLOPES GREATER THAN 2:1.

EROSION CONTROL BLANKET: SHALL BE INSTALLED SUCH THAT CONTINUOUS CONTACT BETWEEN THE MAT AND THE SOIL IS OBTAINED. INSTALL BLANKETS AND STAPLE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

2. SOIL STOCKPILES:

STOCKPILES OF SOIL OR SUBSOIL SHALL BE MULCHED WITH HAY OR STRAW AT A RATE OF 75 LBS/1.000 S.F. (1.5 TONS PER ACRE) OR WITH A FOUR-INCH LAYER OF WOOD WASTE EROSION CONTROL MIX. THIS WILL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL. ANY SOIL STOCKPILE WILL NOT BE PLACED (EVEN COVERED WITH HAY OR STRAW) WITHIN 100 FEET FROM ANY NATURAL RESOURCES. SEDIMENT BARRIERS SHALL BE INSTALLED DOWNGRADIENT OF STOCKPILES, AND STORMWATER SHALL BE PREVENTED FROM RUNNING ONTO THE STOCKPILE.

NATURAL RESOURCES PROTECTION:

ANY AREAS WITHIN 100 FEET FROM ANY NATURAL RESOURCES SHALL BE MULCHED USING TEMPORARY MULCHING (AS DESCRIBED IN PART 1 OF THIS SECTION) WITHIN 7 DAYS OF EXPOSURE OR PRIOR TO ANY STORM EVENT. SEDIMENT BARRIERS (AS DESCRIBED IN PART 4 OF THIS SECTION) SHALL BE PLACED BETWEEN ANY NATURAL RESOURCE AND THE DISTURBED AREA. PROJECTS CROSSING THE NATURAL RESOURCE SHALL BE PROTECTED A MINIMUM DISTANCE OF 100 FEET ON EITHER SIDE FROM THE RESOURCE.

4. SEDIMENT BARRIERS:

PRIOR TO THE BEGINNING OF ANY CONSTRUCTION, SEDIMENT BARRIERS SHALL BE STAKED ACROSS THE SLOPE(S), ON THE CONTOUR AT OR JUST BELOW THE LIMITS OF CLEARING OR GRUBBING, AND/OR JUST ABOVE ANY ADJACENT PROPERTY LINE OR WATERCOURSE TO PROTECT AGAINST CONSTRUCTION RELATED EROSION. SEDIMENT BARRIERS SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL ALL EXPOSED SLOPES HAVE AT LEAST 90% VIGOROUS PERENNIAL VEGETATIVE COVER TO PREVENT FROSION

ILT FENCE: SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. THE EFFECTIVE HEIGHT OF THE FENCE SHALL NOT EXCEED 36 INCHES. IT IS RECOMMENDED THAT SILT FENCE BE REMOVED BY CUTTING THE FENCE MATERIALS AT GROUND LEVEL SO AS TO AVOID ADDITIONAL SOIL DISTURBANCE. HAY BALES: SHALL NOT BE INSTALLED ADJACENT TO WETLAND. INSTALL PER THE DETAIL ON THE PLANS. BALES SHALL BE WIRE-BOUND OR STRING-TIED AND THESE

BINDINGS MUST REMAIN PARALLEL WITH THE GROUND SURFACE DURING INSTALLATION TO PREVENT DETERIORATION OF THE BINDINGS. BALES SHALL BE INSTALLED WITHIN A MINIMUM 4 INCH DEEP TRENCH LINE WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER.

EROSION CONTROL MIX: SHALL NOT BE USED ADJACENT TO WETLANDS. INSTALL PER THE DETAIL ON THE PLANS. THE MIX SHALL CONSIST PRIMARILY OF ORGANIC THE STANDARDS DESCRIBED WITHIN THE MDEP BEST MANAGEMENT PRACTICES. NO TRENCHING IS REQUIRED FOR INSTALLATION OF THIS BARRIER. EROSION CONTROL MIX BERMS SHALL NOT BE USED AT THE BOTTOM OF STEEP SLOPES (>8%) OR SLOPES WITH FLOWING WATER.

CONTINUOUS CONTAINED BERM: SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. THIS SEDIMENT BARRIER IS EROSION CONTROL MIX PLACED WITHIN A SYNTHETIC FUBULAR NETTING AND PERFORMS AS A STURDY SEDIMENT BARRIER THAT WORKS WELL ON HARD GROUND SUCH AS FROZEN CONDITIONS, TRAVELED AREAS OR PAVEMENT. NO TRENCHING IS REQUIRED FOR INSTALLATION OF THIS BARRIER.

TEMPORARY CHECK DAMS:

SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. CHECK DAMS ARE TO BE PLACED WITHIN DITCHES/ SWALES AS SPECIFIED ON THE DESIGN PLANS IMMEDIATELY AFTER FINAL GRADING. CHECK DAMS SHALL BE 2 FEET HIGH. TEMPORARY CHECK DAMS MAY BE REMOVED ONLY AFTER THE ROADWAYS ARE PAVED AND THE VEGETATED SWALE ARE ESTABLISHED WITH AT LEAST 90% OF VIGOROUS PERENNIAL GROWTH. THE AREA BENEATH THE CHECK DAM MUST BE SEEDED AND MULCHED IMMEDIATELY AFTER REMOVAL OF THE CHECK DAM.

STONE CHECK DAMS: STONE DAMS SHOULD BE CONSTRUCTED OF 2 TO 3 INCH STONE AND PLACED SUCH THAT COMPLETE COVERAGE OF THE SWALE IS OBTAINED AND THAT THE CENTER OF THE DAM IS 6 INCHES LOWER THAT THE OUTER EDGES.

HAY BALE CHECK DAMS: BALES SHALL BE WIRE-BOUND OR STRING-TIED. BALES SHALL BE INSTALLED WITHIN A MINIMUM 4 INCH DEEP TRENCH LINE WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER. HAY BALES SHALL BE PLACED SUCH THAT COMPLETE COVERAGE OF THE SWALE IS OBTAINED AND THAT THE CENTER OF THE DAM IS 6 INCHES LOWER THAT THE OUTER EDGES.

MANUFACTURED CHECK DAMS: MANUFACTURED CHECK DAMS, AS SPECIFIED IN THE DETAIL ON THE PLANS, MAY BE USED IF AUTHORIZED BY THE PROPER LOCAL, STATE OR FEDERAL REGULATING AGENCIES. THESE UNITS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURE'S RECOMMENDATIONS.

6. STORMDRAIN INLET PROTECTION:

INLET PROTECTION SHALL BE PLACED AROUND A STORMDRAIN DROP INLET OR CURB INLET PRIOR TO PERMANENT STABILIZATION OF THE IMMEDIATE AND UPSTREAM DISTURBED AREAS. THEY SHALL BE CONSTRUCTED IN A MANNER THAT WILL FACILITATE CLEAN-OUT AND DISPOSAL OF TRAPPED SEDIMENTS AND MINIMIZE INTERFERENCE WITH CONSTRUCTION ACTIVITIES. ANY RESULTANT PONDING OF WATER FROM THE PROTECTION METHOD MUST NOT CAUSE EXCESSIVE INCONVENIENCE OR DAMAGE TO ADJACENT AREAS OR STRUCTURES.

HAY BALE DROP INLET PROTECTION: WE DO NOT RECOMMEND THE USE OF HAY BALES AS INLET PROTECTION.

CONCRETE BLOCK AND STONE INLET SEDIMENT FILTER (DROP OR CURB INLET): SHALL BE INSTALLED PER THE DETAIL ON THE PLANS. THE HEIGHT OF THE CONCRETE BLOCK BARRIER CAN VARY BUT MUST BE BETWEEN 12 AND 24 INCHES TALL. A MINIMUM OF 1 INCH CRUSHED STONE SHALL BE USED.

MANUFACTURED SEDIMENT BARRIERS AND FILTER (DROP OR CURB INLET): MANUFACTURED FILTERS, AS SPECIFIED IN THE DETAIL ON THE PLANS, MAY BE USED IF INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

STABILIZED CONSTRUCTION ENTRANCE/EXIT:

PRIOR TO CLEARING AND/OR GRUBBING THE SITE A STABILIZED CONSTRUCTION ENTRANCE/EXIT SHALL BE CONSTRUCTED WHEREVER TRAFFIC WILL EXIT THE CONSTRUCTION SITE ONTO A PAVED ROADWAY IN ORDER TO MINIMIZE THE TRACKING OF SEDIMENT AND DEBRIS FROM THE CONSTRUCTION SITE ONTO PUBLIC ROADWAYS. THE ENTRANCES AND ADJACENT ROADWAY AREAS SHALL BE PERIODICALLY SWEPT TO FURTHER MINIMIZE THE TRACKING OF MUD, DUST OR DEBRIS FROM THE CONSTRUCTION AREA. THE TERM "SWEEP" IS UNDERSTOOD TO MEAN REMOVAL AND RECOVERY OF TRACKED SEDIMENT WITH A STREET SWEEPER. NOT BRUSHING THE MATERIAL INTO SWALES OR STRUCTURES WITH A MECHANICAL BROOM. STABILIZED CONSTRUCTION EXITS SHALL BE CONSTRUCTED IN AREAS SPECIFIED ON THE PLANS AND AS DETAILED ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN THE STABILIZED CONSTRUCTION ENTRANCE UNTIL ALL DISTURBED AREAS ARE STABILIZED.

DUST CONTROL:

DUST CONTROL DURING CONSTRUCTION SHALL BE ACHIEVED BY THE USE OF A WATERING TRUCK TO PERIODICALLY SPRINKLE THE EXPOSED ROADWAY AREAS AS NECESSARY TO REDUCE DUST DURING THE DRY MONTHS. APPLYING OTHER DUST CONTROL PRODUCTS SUCH AS CALCIUM CHLORIDE OR OTHER MANUFACTURED PRODUCTS ARE ALLOWED IF AUTHORIZED BY THE PROPER LOCAL, STATE AND/OR FEDERAL REGULATING AGENCIES. HOWEVER, IT IS THE CONTRACTOR'S ULTIMATE RESPONSIBILITY TO MITIGATE DUST AND SOIL LOSS FROM THE SITE. IF OFFSITE TRACKING OCCURS, PUBLIC ROADS SHOULD BE SWEPT IMMEDIATELY AND NOT LESS THAN ONCE A WEEK AND PRIOR TO SIGNIFICANT STORM EVENTS.

TEMPORARY VEGETATION:

TEMPORARY VEGETATION SHALL BE APPLIED TO DISTURBED AREAS THAT WILL NOT RECEIVE FINAL GRADING FOR PERIODS UP TO 12 MONTHS. THIS PROCEDURE SHOULD BE USED EXTENSIVELY IN AREAS ADJACENT TO NATURAL RESOURCES. SEEDBED PREPARATION AND APPLICATION OF SEED SHALL BE CONDUCTED AS INDICATED IN THE PERMANENT VEGETATION SECTION OF THIS NARRATIVE. SPECIFIC SEEDS (FAST GROWING AND SHORT LIVING) SHALL BE SELECTED FROM THE MAINE EROSION AND SEDIMENT CONTROL BMP MANUALS FOR CONTRACTORS AND ENGINEERS. LATEST REVISION. ALTERNATIVE EROSION CONTROL MEASURES SHOULD BE USED IF SEEDING CAN NOT BE DONE BEFORE SEPTEMBER 15TH OF THE CONSTRUCTION YEAR.

PERMANENT VEGETATION:

REVEGETATION MEASURES SHALL COMMENCE IMMEDIATELY UPON COMPLETION OF FINAL GRADING OF AREAS TO BE LOAMED AND SEEDED. THE APPLICATION OF SEED SHALL BE CONDUCTED BETWEEN APRIL 1ST AND OCTOBER 1ST OF THE CONSTRUCTION YEAR, PLEASE REFER TO THE WINTER EROSION CONTROL NOTES FOR MORE DETAIL. REVEGETATION MEASURES SHALL CONSIST OF THE FOLLOWING

SEEDBED PREPARATION:

A. FOUR (4) INCHES OF LOAM SHALL BE SPREAD OVER DISTURBED AREAS AND SMOOTHED TO A UNIFORM SURFACE. LOAM SHALL BE FREE OF SUBSOIL, CLAY LUMPS. STONES AND OTHER OBJECTS OVER 2 INCHES OR LARGER IN ANY DIMENSION, AND WITHOUT WEEDS, ROOTS OR OTHER OBJECTIONABLE MATERIAL

B. SOILS TESTS SHALL BE TAKEN AT THE TIME OF SOIL STRIPPING TO DETERMINE FERTILIZATION REQUIREMENTS. SOILS TESTS SHALL BE TAKEN PROMPTLY AS TO NOT INTERFERE WITH THE 14-DAY LIMIT ON SOIL EXPOSURE. BASED UPON TEST RESULTS, SOIL AMENDMENTS SHALL BE INCORPORATED INTO THE SOIL PRIOR TO FINAL SEEDING. IN LIEU OF SOIL TESTS, SOIL AMENDMENTS MAY BE APPLIED AS FOLLOWS:

> ITEM 10-20-20 FERTILIZER (N-P205-K20 OR EQUAL)

APPLICATION RATE 18.4 LBS./1,000 S.F.

138 LBS./1.000 S.F

GROUND LIMESTONE (50% CALCIUM & MAGNESIUM OXIDE)

C. WORK LIME AND FERTILIZER INTO THE SOIL AS NEARLY AS PRACTICAL TO A DEPTH OF 4 INCHES WITH PROPER EQUIPMENT. ROLL THE AREA TO FIRM THE SEEDBED EXCEPT ON CLAY OR SILTY SOILS OR COARSE SAND.

APPLICATION OF SEED:


A. SEEDING: SHALL BE CONDUCTED BETWEEN APRIL 1ST AND OCTOBER 1ST OF THE CONSTRUCTION YEAR. GENERALLY A SEED MIXTURE MAY BE APPLIED AS FOLLOWS: CONSERVATION MIX)

SEED TYPE
FESCUE, FAWN
BIRD'S FOOT TREFOIL, VARIETY NOT STATED
ANNUAL RYEGRASS
TIMOTHY, CLIMAX
ALSIKE CLOVER
REDTOP

STANDARDS FOR TIMELY STABILIZATION:

FOR LATE FALL AND WINTER.

HOUSEKEEPING:



NOTE: A SPECIFIC SEED MIXTURE SHOULD BE CHOSEN TO MATCH THE SOILS CONDITION OF THE SITE. VARIOUS AGENCIES CAN RECOMMEND SEED MIXTURES. MDEP RECOMMENDED SEED MIXTURES ARE IN THE EROSION AND SEDIMENT CONTROL BMP MANUAL DATED 2016 OR LATEST REVISION.

B. HYDROSEEDING: SHALL BE CONDUCTED ON PREPARED AREAS WITH SLOPES LESS THAN 2:1. LIME AND FERTILIZER MAY BE APPLIED SIMULTANEOUSLY WITH THE SEED. COMMENDED SEEDING RATES MUST BE INCREASED BY 10% WHEN HYDROSEEDING.

C. MULCHING: SHALL COMMENCE IMMEDIATELY AFTER SEED IS APPLIED. REFER TO THE TEMPORARY MULCHING SECTION OF THIS NARRATIVE FOR DETAILS.

FOLLOWING SEEDBED PREPARATION, SOD CAN BE APPLIED IN LIEU OF SEEDING IN AREAS WHERE IMMEDIATE VEGETATION IS MOST BENEFICIAL SUCH AS DITCHES, AROUND STORMWATER DROP INLETS AND AREAS OF AESTHETIC VALUE, SOD SHOULD BE LAID AT RIGHT ANGLES TO THE DIRECTION OF FLOW. STARTING AT THE LOWEST ELEVATION. SOD SHOULD BE ROLLED OR TAMPED DOWN TO EVEN OUT THE JOINTS ONCE LAID DOWN. WHERE FLOW IS PREVALENT THE SOD MUST BE PROPERLY ANCHORED DOWN. IRRIGATE THE SOD IMMEDIATELY AFTER INSTALLATION. IN MOST CASES, SOD CAN BE ESTABLISHED BETWEEN APRIL 1ST AND NOVEMBER 15TH OF THE CONSTRUCTION YEAR, HOWEVER, REFER TO THE WINTER EROSION CONTROL NOTES FOR ANY ACTIVITIES AFTER OCTOBER 1ST.

STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SLOPES -- THE CONTRACTOR WILL CONSTRUCT AND STABILIZE STONE-COVERED SLOPES BY NOVEMBER 15. THE CONTRACTOR WILL SEED AND MULCH ALL SLOPES TO BE VEGETATED BY SEPTEMBER 15. THE MDEP WILL CONSIDER ANY AREA HAVING A GRADE GREATER THAN 15% (10H:1V) TO BE A SLOPE. IF THE CONTRACTOR FAILS TO STABILIZE ANY SLOPE TO BE VEGETATED BY SEPTEMBER 15, THEN THE CONTRACTOR WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SLOPE FOR LATE FALL AND WINTER

A. STABILIZE THE SOIL WITH TEMPORARY VEGETATION AND EROSION CONTROL MATS -- BY OCTOBER 1 THE CONTRACTOR WILL SEED THE DISTURBED SLOPE WITH WINTER RYE AT A EDING RATE OF 3 POUNDS PER 1,000 SQUARE FEET AND APPLY EROSION CONTROL MATS OVER THE MULCHED SLOPE. THE CONTRACTOR WILL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SLOPE BY NOVEMBER 1, THEN THE APPLICANT WILL COVER THE SLOPE WITH A LAYER OF WOOD WASTE COMPOST AS DESCRIBED IN ITEM 2(C.) OF THIS STANDARD OR WITH STONE RIPRAP AS DESCRIBED IN ITEM 2(D.) OF THIS STANDARD B. STABILIZE THE SLOPE WITH SOD -- THE CONTRACTOR WILL STABILIZE THE DISTURBED SLOPE WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES

THE APPLICANT PINNING THE SOD ONTO THE SLOPE WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. THE APPLICANT WILL NOT USE LATE-SEASON SOD INSTALLATION TO STABILIZE SLOPES HAVING A GRADE GREATER THAN 33% (3H·1V)

C. STABILIZE THE SLOPE WITH WOOD WASTE COMPOST -- THE CONTRACTOR WILL PLACE A SIX-INCH LAYER OF WOOD WASTE COMPOST ON THE SLOPE BY NOVEMBER 15. PRIOR TO LACING THE WOOD WASTE COMPOST, THE APPLICANT WILL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED SLOPE. THE APPLICANT WILL NOT USE WOOD WASTE COMPOST TO STABILIZE SLOPES HAVING GRADES GREATER THAN 50% (2H:1V) OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE. D. STABILIZE THE SLOPE WITH STONE RIPRAP -- THE CONTRACTOR WILL PLACE A LAYER OF STONE RIPRAP ON THE SLOPE BY NOVEMBER 15. THE APPLICANT WILL HIRE A GISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE NEEDED FOR STABILITY AND TO DESIGN A FILTER LAYER FOR UNDERNEATH THE RIPRAP.

STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SOILS -- BY SEPTEMBER 15 THE CONTRACTOR WILL SEED AND MULCH ALL DISTURBED SOILS ON AREAS HAVING A SLOPE LESS THAN 15%. IF THE CONTRACTOR FAILS TO STABILIZE THESE SOILS BY THIS DATE, THEN THE CONTRACTOR WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SOIL

A. STABILIZE THE SOIL WITH TEMPORARY VEGETATION -- BY OCTOBER 1 THE CONTRACTOR WILL SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET, LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 POUNDS PER 1000 SQUARE FEET, AND ANCHOR THE MULCH WITH PLASTIC NETTING. THE APPLICANT WILL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SOIL BEFORE NOVEMBER 15, THEN THE APPLICANT WILL MULCH THE AREA FOR OVER-WINTER PROTECTION AS DESCRIBED IN ITEM 3(C.) OF THIS STANDARD STABILIZE THE SOIL WITH SOD -- THE APPLICANT WILL STABILIZE THE DISTURBED SOIL WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES THE LICANT PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. STABILIZE THE SOLUTION WITH MULCH -- BY NOVEMBER 15 THE APPLICANT WILL MULCH THE DISTURBED SOLUBY SPREADING HAY OR STRAW AT A RATE OF AT LEAST 150 POLINDS PER 1000 SQUARE FEET ON THE AREA SO THAT NO SOIL IS VISIBLE THROUGH THE MULCH. PRIOR TO APPLYING THE MULCH, THE APPLICANT WILL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED AREA. IMMEDIATELY AFTER APPLYING THE MULCH, THE APPLICANT WILL ANCHOR THE MULCH WITH PLASTIC NETTING TO PREVENT WIND FROM MOVING THE MULCH OFF THE DISTURBED SOIL.

1. MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION CYCLE. AFTER EACH RAINFALL, SNOW STORM OR PERIOD OF THAWING AND RUNOFF, AND AT LEAST EVERY SEVEN (7) DAYS, THE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL INSTALLED EROSION CONTROL MEASURES. THE CONTRACTOR SHALL PERFORM REPAIRS NO LATER THAN THE END OF THE NEXT WORKDAY, TO ALLOW CONTINUED PROPER FUNCTIONING OF THE EROSION CONTROL MEASURE. THE CONTRACTOR SHALL PROVIDE THE NECESSARY REGULATING AGENCIES WITH WRITTEN DOCUMENTATION DESCRIBING DATES OF INSPECTIONS AND NECESSARY FOLLOW-UP WORK TO MAINTAIN EROSION CONTROL MEASURES MEETING THE REQUIREMENTS OF THIS PLAN WITHIN SEVEN (7) DAYS.

2. FOLLOWING THE TEMPORARY AND/OR FINAL SEEDINGS, THE CONTRACTOR SHALL INSPECT THE WORK AREA SEMIMONTHLY UNTIL THE SEEDINGS HAVE BEEN ESTABLISHED. ESTABLISHED MEANS A MINIMUM OF 90% OF AREAS VEGETATED WITH VIGOROUS GROWTH. RESEEDING SHALL BE CARRIED OUT BY THE CONTRACTOR WITH FOLLOW-UP INSPECTIONS IN THE EVENT OF ANY FAILURES UNTIL VEGETATION IS ADEQUATELY ESTABLISHED.

1. SPILL PREVENTION. CONTROLS MUST BE USED TO PREVENT POLLUTANTS FROM CONSTRUCTION AND WASTE MATERIALS STORED ON SITE TO ENTER STORMWATER, WHICH INCLUDES STORAGE PRACTICES TO MINIMIZE EXPOSURE OF THE MATERIALS TO STORMWATER. THE SITE CONTRACTOR OR OPERATOR MUST DEVELOP, AND IMPLEMENT AS NECESSARY, APPROPRIATE SPILL PREVENTION, CONTAINMENT, AND RESPONSE PLANNING MEASURES.

2. GROUNDWATER PROTECTION. DURING CONSTRUCTION, LIQUID PETROLEUM PRODUCTS AND OTHER HAZARDOUS MATERIALS WITH THE POTENTIAL TO CONTAMINATE GROUNDWATER MAY NOT BE STORED OR HANDLED IN AREAS OF THE SITE DRAINING TO AN INFILTRATION AREA. AN "INFILTRATION AREA" IS ANY AREA OF THE SITE THAT BY DESIGN OR AS A RESULT OF SOILS, TOPOGRAPHY AND OTHER RELEVANT FACTORS ACCUMULATES RUNOFF THAT INFILTRATES INTO THE SOIL, DIKES, BERMS, SUMPS, AND OTHER FORMS OF SECONDARY CONTAINMENT THAT PREVENT DISCHARGE TO GROUNDWATER MAY BE USED TO ISOLATE PORTIONS OF THE SITE FOR THE PURPOSES OF STORAGE AND HANDLING OF THESE MATERIALS. ANY PROJECT PROPOSING INFILTRATION OF STORMWATER MUST PROVIDE ADEQUATE PRE-TREATMENT OF STORMWATER PRIOR TO DISCHARGE OF STORMWATER TO THE INFILTRATION AREA, OR PROVIDE FOR TREATMENT WITHIN THE INFILTRATION AREA, IN ORDER TO PREVENT THE ACCUMULATION OF FINES, REDUCTION IN INFILTRATION RATE, AND CONSEQUENT FLOODING AND DESTABILIZATION.

3. FUGITIVE SEDIMENT AND DUST. ACTIONS MUST BE TAKEN TO ENSURE THAT ACTIVITIES DO NOT RESULT IN NOTICEABLE EROSION OF SOILS OR FUGITIVE DUST EMISSIONS DURING OR AFTER CONSTRUCTION. OIL MAY NOT BE USED FOR DUST CONTROL, BUT OTHER WATER ADDITIVES MAY BE CONSIDERED AS NEEDED. A STABILIZED CONSTRUCTION ENTRANCE (SCE) SHOULD BE INCLUDED TO MINIMIZE TRACKING OF MUD AND SEDIMENT. IF OFF-SITE TRACKING OCCURS, PUBLIC ROADS SHOULD BE SWEPT IMMEDIATELY AND NO LESS THAN ONCE A WEEK AND PRIOR TO SIGNIFICANT STORM EVENTS. OPERATIONS DURING DRY MONTHS, THAT EXPERIENCE FUGITIVE DUST PROBLEMS, SHOULD WET DOWN UNPAVED ACCESS ROADS ONCE A WEEK OR MORE FREQUENTLY AS NEEDED WITH A WATER ADDITIVE TO SUPPRESS FUGITIVE SEDIMENT AND DUST.

4. DEBRIS AND OTHER MATERIALS. MINIMIZE THE EXPOSURE OF CONSTRUCTION DEBRIS, BUILDING AND LANDSCAPING MATERIALS, TRASH, FERTILIZERS, PESTICIDES, HERBICIDES, DETERGENTS, SANITARY WASTE AND OTHER MATERIALS TO PRECIPITATION AND STORMWATER RUNOFF. THESE MATERIALS MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE.

5. EXCAVATION DE-WATERING. EXCAVATION DE-WATERING IS THE REMOVAL OF WATER FROM TRENCHES, FOUNDATIONS, COFFER DAMS, PONDS, AND OTHER AREAS WITHIN THE CONSTRUCTION AREA THAT RETAIN WATER AFTER EXCAVATION. IN MOST CASES THE COLLECTED WATER IS HEAVILY SILTED AND HINDERS CORRECT AND SAFE CONSTRUCTION PRACTICES. THE COLLECTED WATER REMOVED FROM THE PONDED AREA. EITHER THROUGH GRAVITY OR PUMPING, MUST BE SPREAD THROUGH NATURAL WOODED BUFFERS OR REMOVED TO AREAS THAT ARE SPECIFICALLY DESIGNED TO COLLECT THE MAXIMUM AMOUNT OF SEDIMENT POSSIBLE, LIKE A COFFERDAM SEDIMENTATION BASIN. AVOID ALLOWING THE WATER TO FLOW OVER DISTURBED AREAS OF THE SITE. EQUIVALENT MEASURES MAY BE TAKEN IF APPROVED BY THE DEPARTMENT.

THORIZED NON-STORMWATER DISCHARGES. IDENTIFY AND PREVENT CONTAMINATION BY NON-STORMWATER DISCHARGES. WHERE ALLOWED NON-STORMWATER DISCHARGES EXIST, THEY MUST BE IDENTIFIED AND STEPS SHOULD BE TAKEN TO ENSURE THE IMPLEMENTATION OF APPROPRIATE POLLUTION PREVENTION MEASURES FOR THE NON-STORMWATER COMPONENT(S) OF THE DISCHARGE. AUTHORIZED NON-STORMWATER DISCHARGES ARE: A. DISCHARGES FROM FIREFIGHTING ACTIVITY;

B. FIRE HYDRANT FLUSHINGS; C. VEHICLE WASHWATER IF DETERGENTS ARE NOT USED AND WASHING IS LIMITED TO THE EXTERIOR OF VEHICLES (ENGINE, UNDERCARRIAGE AND TRANSMISSION WASHING IS PROHIBITED) DUST CONTROL RUNOFF IN ACCORDANCE WITH PERMIT CONDITIONS;

ROUTINE EXTERNAL BUILDING WASHDOWN, NOT INCLUDING SURFACE PAINT REMOVAL, THAT DOES NOT INVOLVE DETERGENTS; F. PAVEMENT WASHWATER (WHERE SPILLS/LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE NOT OCCURRED, UNLESS ALL SPILLED MATERIAL HAD BEEN REMOVED) IF

DETERGENTS ARE NOT USED: G. UNCONTAMINATED AIR CONDITIONING OR COMPRESSOR CONDENSATE; H. UNCONTAMINATED GROUNDWATER OR SPRING WATER;

I. FOUNDATION OR FOOTER DRAIN-WATER WHERE FLOWS ARE NOT CONTAMINATED; J. UNCONTAMINATED EXCAVATION DEWATERING:

K. POTABLE WATER SOURCES INCLUDING WATERLINE FLUSHINGS; AND L. LANDSCAPE IRRIGATION.

7. UNAUTHORIZED NON-STORMWATER DISCHARGES. THE DEPARTMENT'S APPROVAL DOES NOT AUTHORIZE A DISCHARGE THAT IS MIXED WITH A SOURCE OF NON-STORMWATER, THER THAN THOSE DISCHARGES. SPECIFICALLY, THE DEPARTMENT'S APPROVAL DOES NOT AUTHORIZE DISCHARGES OF THE FOLLOWING A. WASTEWATER FROM THE WASHOUT OR CLEAN OUT OF CONCRETE, STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS OR OTHER CONSTRUCTION MATERIALS; B. FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE: SOAPS. SOLVENTS. OR DETERGENTS USED IN VEHICLE AND EQUIPMENT WASHING; AND D. TOXIC OR HAZARDOUS SUBSTANCES FROM A SPILL OR OTHER RELEASE

THE WINTER CONSTRUCTION PERIOD IS FROM NOVEMBER 1 THROUGH APRIL 15. IF THE CONSTRUCTION SITE IS NOT STABILIZED WITH PAVEMENT, A ROAD GRAVEL BASE,

75% MATURE VEGETATION COVER OR RIPRAP BY NOVEMBER 1 THEN THE SITE NEEDS TO BE PROTECTED WITH OVER-WINTER STABILIZATION. AN AREA CONSIDERED OPEN IS ANY AREA NOT STABILIZED WITH PAVEMENT, VEGETATION, MULCHING, EROSION CONTROL MATS, RIPRAP OR GRAVEL BASE ON A ROAD. LIMIT THE EXPOSED AREA TO THOSE AREAS IN WHICH WORK IS EXPECTED TO BE UNDER TAKEN DURING THE PROCEEDING 15 DAYS AND THAT CAN BE MULCHED IN ONE DAY PRIOR TO ANY SNOW EVENT. ALL AREAS SHALL BE CONSIDERED TO BE DENUDED UNTIL THE SUBBASE GRAVEL IS INSTALLED IN ROADWAY AREAS OR THE AREAS OF FUTURE LOAM AND SEED HAVE BEEN LOAMED, SEEDED AND MULCHED. HAY AND STRAW MULCH RATE SHALL BE A MINIMUM OF 150 LBS./1,000 S.F. (3 TONS/ACRE) AND SHALL BE PROPERLY ANCHORED. THE CONTRACTOR MUST INSTALL ANY ADDED MEASURES WHICH MAY BE NECESSARY TO CONTROL EROSION/SEDIMENTATION FROM THE SITE DEPENDENT UPON THE ACTUAL SITE AND WEATHER CONDITIONS. CONTINUATION OF EARTHWORK OPERATIONS ON ADDITIONAL AREAS SHALL NOT BEGIN UNTIL THE EXPOSED SOIL SURFACE ON THE AREA BEING WORKED HAS BEEN STABILIZED, IN ORDER TO MINIMIZE AREAS WITHOUT EROSION CONTROL PROTECTION. 1. SOIL STOCKPILES

STOCKPILES OF SOIL OR SUBSOIL WILL BE MULCHED FOR OVER WINTER PROTECTION WITH HAY OR STRAW AT TWICE THE NORMAL RATE OR AT 150 LBS/1,000 S.F. (3 TONS PER ACRE) OR WITH A FOUR-INCH LAYER OF WOOD WASTE EROSION CONTROL MIX. THIS WILL BE DONE WITHIN 24 HOURS OF STOCKING AND RE-ESTABLISHED PRIOR TO ANY RAINFALL OR SNOWFALL. ANY SOIL STOCKPILE WILL NOT BE PLACED (EVEN COVERED WITH HAY OR STRAW) WITHIN 100 FEET FROM ANY NATURAL RESOURCES.

ANY AREAS WITHIN 100 FEET FROM ANY NATURAL RESOURCES. IF NOT STABILIZED WITH A MINIMUM OF 75% MATURE VEGETATION CATCH. SHALL BE MULCHED BY DECEMBER 1 AND ANCHORED WITH PLASTIC NETTING OR PROTECTED WITH EROSION CONTROL MATS. DURING WINTER CONSTRUCTION, A DOUBLE LINE OF SEDIMENT BARRIERS (I.E. SILT FENCE BACKED WITH HAY BALES OR EROSION CONTROL MIX) WILL BE PLACED BETWEEN ANY NATURAL RESOURCE AND THE DISTURBED AREA. PROJECTS CROSSING THE NATURAL RESOURCE SHALL BE PROTECTED A MINIMUM DISTANCE OF 100 FEET ON EITHER SIDE FROM THE RESOURCE. EXISTING PROJECTS NOT STABILIZED BY DECEMBER 1 SHALL BE PROTECTED WITH THE SECOND LINE OF SEDIMENT BARRIER TO ENSURE FUNCTIONALITY DURING THE SPRING THAW AND

3. SEDIMENT BARRIERS

4. MULCHING

ALL AREA SHALL BE CONSIDERED TO BE DENUDED UNTIL AREAS OF FUTURE LOAM AND SEED HAVE BEEN LOAMED, SEEDED AND MULCHED. HAY AND STRAW MULCH SHALL BE APPLIED AT A RATE OF 150 LB. PER 1.000 SQUARE FEET OR 3 TONS/ACRE (TWICE THE NORMAL ACCEPTED RATE OF 75-LBS./1,000 S.F. OR 1.5 TONS/ACRE) AND SHALL BE PROPERLY ANCHORED. MULCH SHALL NOT BE SPREAD ON TOP OF SNOW. THE SNOW WILL BE REMOVED DOWN TO A ONE-INCH DEPTH OR LESS PRIOR TO APPLICATION, AFTER EACH DAY OF FINAL GRADING, THE AREA WILL BE PROPERLY STABILIZED WITH ANCHORED HAY OR STRAW OR EROSION CONTROL MATTING. AN AREA SHALL BE CONSIDERED TO HAVE BEEN STABILIZED WHEN EXPOSED SURFACES HAVE BEEN EITHER MULCHED WITH STRAW OR HAY AT A RATE OF 150 LB. PER 1.000 SQUARE FEET (3TONS/ACRE) AND ADEQUATELY ANCHORED THAT GROUND SURFACE IS NOT VISIBLE THOUGH THE MULCH.

BETWEEN THE DATES OF SEPTEMBER 1 AND APRIL 15, ALL MULCH SHALL BE ANCHORED BY EITHER PEG LINE, MULCH NETTING, ASPHALT EMULSION CHEMICAL, TRACK OR WOOD CELLULOSE FIBER. WHEN GROUND SURFACE IS NOT VISIBLE THOUGH THE MULCH THEN COVER IS SUFFICIENT AFTER NOVEMBER 1ST, MULCH AND ANCHORING OF ALL BARE SOIL SHALL OCCUR AT THE END OF EACH FINAL GRADING WORK DAY.

SLOPES SHALL NOT BE LEFT EXPOSED FOR ANY EXTENDED TIME OF WORK SUSPENSION UNLESS FULLY MULCHED AND ANCHORED WITH PEG AND NETTING OR WITH EROSION CONTROL BLANKETS, MULCHING SHALL BE APPLIED AT A RATE OF 230 LBS/1.000 S.F. ON ALL SLOPES GREATER THAN 8%, MULCH NETTING SHALL BE USED TO ANCHOR MULCH IN ALL DRAINAGE WAYS WITH A SLOPE GREATER THAN 3% FOR SLOPES EXPOSED TO DIRECT WINDS AND FOR ALL OTHER SLOPES GREATER THAN 5%. EROSION CONTROL BLANKETS SHALL BE USED IN LIEU OF MULCH IN ALL DRAINAGE WAYS WITH SLOPES 8%. EROSION CONTROL MIX CAN BE USED TO SUBSTITUTE EROSION CONTROL BLANKETS ON ALL SLOPES EXCEPT DITCHES. 6. SEEDING

BETWEEN THE DATES OF OCTOBER 15 AND APRIL 1ST, LOAM OR SEED WILL NOT BE REQUIRED. DURING PERIODS OF ABOVE FREEZING TEMPERATURES FINISHED AREAS SHALL BE FINE GRADED AND EITHER PROTECTED WITH MULCH OR TEMPORARILY SEEDED AND MULCHED UNTIL SUCH TIME AS THE FINAL TREATMENT CAN BE APPLIED. IF THE DATE IS AFTER NOVEMBER 1ST AND IF THE EXPOSED AREA HAS BEEN LOOMED, FINAL GRADED WITH A UNIFORM SURFACE, THEN THE AREA MAY BE DORMANT SEEDED AT A RATE OF 3 TIMES HIGHER THAN SPECIFIED FOR PERMANENT SEED AND THEN MULCHED. DORMANT SEEDING MAY BE SELECTED TO BE PLACED PRIOR TO THE PLACEMENT OF MULCH AND FABRIC NETTING ANCHORED WITH STAPLES. IF DORMANT SEEDING IS USED FOR THE SITE, ALL DISTURBED AREAS SHALL RECEIVE 4' OF LOAM AND SEED AT AN APPLICATION RATE OF 5LBS/1000 S.F. ALL AREAS SEEDED DURING THE WINTER WILL BE INSPECTED IN THE SPRING FOR ADEQUATE CATCH. ALL AREAS SUFFICIENTLY VEGETATED (LESS THAN 75% CATCH) SHALL BE REVEGETATED BY REPLACING LOAM, SEED AND MULCH. IF DORMANT SEEDING IS NOT USED FOR THE SITE, ALL DISTURBED AREAS SHALL BE REVEGETATED IN THE SPRING. SEED TYPE SHALL BE WINTER RYE.

7. INSPECTION AND MONITORING

STANDARDS FOR TIMELY STABILIZATION OF CONSTRUCTION SITES DURING WINTER

1. STANDARD FOR THE TIMELY STABILIZATION OF DITCHES AND CHANNELS -- THE APPLICANT WILL CONSTRUCT AND STABILIZE ALL STONE-LINED DITCHES AND CHANNELS ON THE SITE BY NOVEMBER 15. THE APPLICANT WILL CONSTRUCT AND STABILIZE ALL GRASS-LINED DITCHES AND CHANNELS ON THE SITE BY SEPTEMBER 15. IF THE APPLICANT FAILS TO STABILIZE A DITCH OR CHANNEL TO BE GRASS-LINED BY SEPTEMBER 15. THEN THE APPLICANT WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE DITCH FOR LATE FALL AND WINTER.

INSTALL A SOD LINING IN THE DITCH -- THE APPLICANT WILL LINE THE DITCH WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION INCLUDES THE APPLICANT PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL, AND ANCHORING THE SOD WITH JUTE OR PLASTIC MESH TO PREVENT THE SOD STRIPS FROM SLOUGHING NSTALL A STONE LINING IN THE DITCH --THE APPLICANT WILL LINE THE DITCH WITH STONE RIPRAP BY NOVEMBER 15. THE APPLICANT WILL HIRE A REGISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE AND LINING THICKNESS NEEDED TO WITHSTAND THE ANTICIPATED FLOW VELOCITIES AND FLOW DEPTHS WITHIN THE DITCH. IF NECESSARY, THE APPLICANT WILL REGRADE THE DITCH PRIOR TO PLACING THE STONE LINING SO TO PREVENT THE STONE LINING FROM REDUCING THE DITCH'S CROSS-SECTIONAL AREA.

2. STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SLOPES -- THE APPLICANT WILL CONSTRUCT AND STABILIZE STONE-COVERED SLOPES BY NOVEMBER 15. THE APPLICANT WILL SEED AND MULCH ALL SLOPES TO BE VEGETATED BY SEPTEMBER 15. THE DEPARTMENT WILL CONSIDER ANY AREA HAVING A GRADE GREATER THAN 15% (10H:1V) TO BE A SLOPE. IF THE APPLICANT FAILS TO STABILIZE ANY SLOPE TO BE VEGETATED BY SEPTEMBER 15, THEN THE APPLICANT WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SLOPE FOR LATE FALL AND WINTER.

STABILIZE THE SOIL WITH TEMPORARY VEGETATION AND EROSION CONTROL MATS -- BY OCTOBER 1 THE APPLICANT WILL SEED THE DISTURBED SLOPE WITH WINTER RYE AT A SEEDING RATE OF 3 POUNDS PER 1000 SQUARE FEET AND APPLY EROSION CONTROL MATS OVER THE MULCHED SLOPE. THE APPLICANT WILL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS TO GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SLOPE BY NOVEMBER 1, THEN THE APPLICANT WILL COVER THE SLOPE WITH A LAYER OF WOOD WASTE COMPOST AS DESCRIBED IN ITEM III OF THIS CONDITION OR WITH STONE RIPRAP AS DESCRIBED IN ITEM IV OF THIS CONDITION. STABILIZE THE SLOPE WITH SOD -- THE APPLICANT WILL STABILIZE THE DISTURBED SLOPE WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION

NCLUDES THE APPLICANT PINNING THE SOD ONTO THE SLOPE WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. THE APPLICANT WILL NOT USE LATE-SEASON SOD INSTALLATION TO STABILIZE SLOPES HAVING A GRADE GREATER THAN 33% (3H:1V).

STABILIZE THE SLOPE WITH WOOD WASTE COMPOST -- THE APPLICANT WILL PLACE A SIX-INCH LAYER OF WOOD WASTE COMPOST ON THE SLOPE BY NOVEMBER 15. PRIOR TO PLACING THE WOOD WASTE COMPOST, THE APPLICANT WILL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED SLOPE. THE APPLICANT WILL NOT USE WOOD WASTE COMPOST TO STABILIZE SLOPES HAVING GRADES GREATER THAN 50% (2H:1V) OR HAVING GROUNDWATER SEEPS ON THE SLOPE FACE.

STABILIZE THE SOIL FOR LATE FALL AND WINTER. THIS STANDARD

WINTER EROSION CONTROL MEASURES

2. NATURAL RESOURCES PROTECTION

DURING FROZEN CONDITIONS, SEDIMENT BARRIERS SHALL CONSIST OF WOOD WASTE FILTER BERMS AS FROZEN SOIL PREVENTS THE PROPER INSTALLATION OF HAY BALES AND SEDIMENT SILT FENCES.

5. MULCHING ON SLOPES AND DITCHES

MAINTENANCE MEASURES SHALL BE APPLIED AS NEEDED DURING THE ENTIRE CONSTRUCTION SEASON. AT A MINIMUM, AFTER EACH RAINFALL, SNOW STORM OR PERIOD OF THAWING AND RUNOFF, THE SITE CONTRACTOR SHALL PERFORM A VISUAL INSPECTION OF ALL INSTALLED EROSION CONTROL MEASURES AND PERFORM REPAIRS AS NEEDED TO INSURE THEIR CONTINUOUS FUNCTION FOLLOWING THE TEMPORARY AND OR FINAL SEEDING AND MULCHING, THE CONTRACTOR SHALL IN THE SPRING INSPECT AND REPAIR ANY DAMAGES AND/ OR UNESTABLISHED SPOTS. ESTABLISHED VEGETATIVE COVER MEANS A MINIMUM OF 90% OF AREAS VEGETATED WITH VIGOROUS GROWTH.

STABILIZE THE SLOPE WITH STONE RIPRAP -- THE APPLICANT WILL PLACE A LAYER OF STONE RIPRAP ON THE SLOPE BY NOVEMBER 15. THE APPLICANT WILL HIRE A REGISTERED PROFESSIONAL ENGINEER TO DETERMINE THE STONE SIZE NEEDED FOR STABILITY AND TO DESIGN A FILTER LAYER FOR UNDERNEATH THE RIPRAP.


3. STANDARD FOR THE TIMELY STABILIZATION OF DISTURBED SOILS -- BY SEPTEMBER 15 THE APPLICANT WILL SEED AND MULCH ALL DISTURBED SOILS ON AREAS HAVING A SLOPE LESS THAN 15%. IF THE APPLICANT FAILS TO STABILIZE THESE SOILS BY THIS DATE, THEN THE APPLICANT WILL TAKE ONE OF THE FOLLOWING ACTIONS TO STABILIZE THE SOIL WITH TEMPORARY VEGETATION -- BY OCTOBER 1 THE APPLICANT WILL SEED THE DISTURBED SOIL WITH WINTER RYE AT A SEEDING RATE OF 3

POUNDS PER 1000 SQUARE FEET, LIGHTLY MULCH THE SEEDED SOIL WITH HAY OR STRAW AT 75 POUNDS PER 1000 SQUARE FEET, AND ANCHOR THE MULCH WITH PLASTIC NETTING. THE APPLICANT WILL MONITOR GROWTH OF THE RYE OVER THE NEXT 30 DAYS. IF THE RYE FAILS GROW AT LEAST THREE INCHES OR COVER AT LEAST 75% OF THE DISTURBED SOIL BEFORE NOVEMBER 15, THEN THE APPLICANT WILL MULCH THE AREA FOR OVER-WINTER PROTECTION AS DESCRIBED IN ITEM III OF


STABILIZE THE SOIL WITH SOD -- THE APPLICANT WILL STABILIZE THE DISTURBED SOIL WITH PROPERLY INSTALLED SOD BY OCTOBER 1. PROPER INSTALLATION NCLUDES THE APPLICANT PINNING THE SOD ONTO THE SOIL WITH WIRE PINS, ROLLING THE SOD TO GUARANTEE CONTACT BETWEEN THE SOD AND UNDERLYING SOIL, AND WATERING THE SOD TO PROMOTE ROOT GROWTH INTO THE DISTURBED SOIL. STABILIZE THE SOIL WITH MULCH -- BY NOVEMBER 15 THE APPLICANT WILL MULCH THE DISTURBED SOIL BY SPREADING HAY OR STRAW AT A RATE OF AT LEAST 150 POUNDS PER 1000 SQUARE FEET ON THE AREA SO THAT NO SOIL IS VISIBLE THROUGH THE MULCH. PRIOR TO APPLYING THE MULCH, THE APPLICANT WILL REMOVE ANY SNOW ACCUMULATION ON THE DISTURBED AREA. IMMEDIATELY AFTER APPLYING THE MULCH, THE APPLICANT WILL ANCHOR THE MULCH WITH PLASTIC NETTING TO PREVENT WIND FROM MOVING THE MULCH OFF THE DISTURBED SOIL.





SHAWN M. FRANK, PE 6396	TONS.
	C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERAT THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERAT AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS
	TECHNICS.COM 75 John Roberts Rd. South Portland, ME 04106 Tel. 207-200-2100
	<u>RECORD OWNER:</u> FREDERICK ROBIE,JR. C/O BRUCE ROBIE 32 BEECHNUT LANE HOLDEN, ME
	EROSION CONTROL NOTES OF: ROBIE STREET SUBDIVISION ROBIE STREET GORHAM, MAINE FOR: FOR: FOR: FOR: FOR: FOR: FOR: FOR:
	DESIGNEDJBPDRAWNSTICHECKEDSMFDATE05/31/2022SCALENTS




WIDTH -W1 (FT)	WIDTH -W2 (FT)	RIPRAP D50 (IN.)	RIPRAP THICKNESS (IN.)
3	9	6	14
4	12	6	14
5	15	7	16
6	20	8	18
9	32	11	25
11	37	12	27
12	43	16	36









NOTES


- 1. LIFT STATION SHALL BE DUPLEX LIFT STATION PANEL AND CONTROLS FOR THE OPERATIONS OF 2.0 HOMA CUTTER PUMPS OPERATING AT APPROXIMATELY THE DUTY POINT LISTED IN THE TABLE BELOW. THE PUMPS ARE MODEL AMS444-285ASC 1 PHASE, 60 HZ, 230 VOLT/460V, 1750 RPM AND 84 FLA/42 FLA WITH THE INSTALLED IMPELLER.
- PUMPS SHALL HAVE BREAK AWAY FITTINGS. BREAK AWAY FITTINGS SHALL BE NON-SPARKING.
- ALL UNDERGROUND ELECTRIC POWER LINES SHALL BE INSTALLED IN PVC 17. COAT EXTERIOR OF STRUCTURES WITH KOPPERS BITUMASTIC 3000 CONDUIT. ABOVE GROUND SERVICES SHALL BE INSTALLED IN SCHEDULE 40 GALVANIZED CONDUIT. SIZES AS REQUIRED BY ELECTRIC COMPANY. ALL ELECTRICAL WIRING SHALL MEET ALL LOCAL AND NEC ELECTRICAL CODE REQUIREMENTS.
- 4. THE PANEL SHALL BE EQUIPPED WITH AN INNER DOOR THAT HAS ELAPSED TIMED METERS, WARNING LIGHTS FOR TEMPERATURE AND MOISTURE SENSORS, CONTROL SWITCHES FOR THE INDIVIDUAL PUMPS (AUTO, OFF AND RUN) AND A CONTROL SWITCH FOR THE ALARM WITH TEST AND SILENCE.
- 5. THE MAIN BREAKERS (CONTROL AND PUMPS) AND FUSES FOR BOTH THE ALARM AND CONTROLS SHALL BE ACCESSIBLE WITHOUT OPENING THE INNER DOOR.
- 6. THE PANEL SHALL HAVE BOTH AMBER VISIBLE ALARM LIGHT AND AN AUDIBLE PIEZO 80DB ALARM. THE ENCLOSURE SHALL BE A FIBERGLASS NEMA 4X RATED, UL698A COMPLIANT LISTED ENCLOSURE RATED FOR THE PUMPS WITH A WIRING SCHEMATIC PROVIDED ON THE INNER FACE OF THE PANEL DOOR. THE DOOR SHALL HAVE A WEATHER SEAL AND LOCKABLE LATCHES.
- 7. THE PANEL SHALL HAVE THE REQUIRED CIRCUITRY, CONTROLLERS, CIRCUIT BREAKERS, DELAYS, MOTOR STARTERS, RELAYS, TERMINAL BLOCK AND GROUNDING REQUIRED TO OPERATE THE PUMPS IN A AN ALTERNATING SEQUENCE. PANEL, CONTROLS AND ELECTRICAL COMPONENTS SHALL BE EXPLOSION PROOF.
- 8. THE PANEL SHALL BE MANUFACTURED BY SJE RHOMBUS, PRIMEX CONTROLS, CSI OR APPROVED EQUIVALENT.
- 9. THE PUMPS, CONTROLS, FLOATS AND FLOAT RACK SHALL BE SUPPLIED BY ONE DISTRIBUTOR OR MANUFACTURER. FLOAT SWITCHES SHALL BE INSTALLED WITH KWIK FLOAT SWITCH CONNECTION SYSTEM. DISTRIBUTOR OR MANUFACTURER SUPPLYING EQUIPMENT SHALL CONFIRM ALL EQUIPMENT MEETS THE INTENT OF THIS SPECIFICATION, AND THAT ALL EQUIPMENT SUPPLIED IS COMPATIBLE FOR THIS SPECIFIC APPLICATION. ALL EQUIPMENT SUPPLIED REQUIRING FACTORY START-UP TO OBTAIN WARRANTY SHALL BE INCLUDED AND PERFORMED BY FACTORY AUTHORIZED PERSONNEL. ANY DEFICIENCIES SHALL BE ADDRESSED PRIOR TO FINAL ACCEPTANCE.
- 10. PUMP POWER/CONTROL CABLES AND FLOAT CABLES SHALL BE ROUTED TO THE WET WELL IN SEPARATE CONDUITS WITH THE PROPER EXPANSION JOINTS, SEAL OFFS, AND EXPANSION JOINTS. PUMP AND FLOAT CABLES SHALL BE WIRED FORM WET WELL DIRECTLY TO PANEL WITH NO INTERMEDIATE JUNCTION BOXES. WIRE SIZING AND CONDUITS FEEDING AND LEAVING THE CONTROL PANEL SHALL BE PROPERLY SIZED, SHALL SUPPORT THE LOAD OF TWO PUMPS OPERATING AND MEET ALL APPLICABLE LOCAL, STATE AND NEC ELECTRICAL CODES.
- 11. PUMPS SHALL BE PROVIDED WITH TEMPERATURE AND MOISTURE SENSORS MATCHED TO THE PUMPS.
- 12. FLOAT CONTROLS SHALL BE NON-MERCURY MECHANICAL FLOATS.
- 13. CONCRETE: 5,000 PSI AFTER 28 DAYS. REINFORCING STEEL MIN. YIELD STRESS OF 40,000 PSI.

- 14. REINFORCING: WALLS & FLOOR 4X4/4X4 W.W.M. SLAB TOP #5 @ 8" O.C.
- 15. THE ACCESS HATCH SHALL BE MANUFACTURED BY THE BILCO COMPANY OR EQUIVALENT AND BE RATED FOR H-20 LOADING. HATCH SHALL OPEN TOWARDS PUMP STATION PANEL AND HAVE INTEGRAL SECONDARY FALL PROTECTION
- 16. ALL LIFT STATION PIPING SHALL BE DIP 350 PSI.
- M OR EQUAL.
- 18. WET WELL SHALL BE INSTALLED ON A MINIMUM 12" BED OF SCREENED GRAVEL.
- 19. CONTRACTOR TO CONFIRM OPERATING ELEVATIONS WITH ENGINEER BEFORE ORDERING STATION.
- 20. CONTRACTOR TO SUBMIT SPECIFICATIONS FOR PUMPS, CONTROL PANELS, AND ALARM FOR OWNER AND ENGINEERS APPROVAL.
- 21. ELECTRIC SERVICES SHALL BE VERIFIED BY CONTRACTOR AND COORDINATED WITH OWNER, ELECTRIC COMPANY AND PUMP STATION MANUFACTURER PRIOR TO INSTALLATION. CONTRACTOR SHALL PROVIDE AND INSTALL ALL ELECTRICAL COMPONENTS REQUIRED FOR PUMP STATION MEETING APPLICABLE STATE, FEDERAL AND LOCAL CODES.
- 22 PRIOR TO CONSTRUCTION, CONTRACTOR SHALL MEET ON-SITE WITH OWNER AND ENGINEER TO REVIEW LOCATION OF PUMP STATION AND VALVE PIT. DEPENDING ON PHYSICAL SITE FEATURES, THE ENGINEER RESERVES THE RIGHT TO MODIFY LOCATION.
- 23. UPON INSTALLATION OF PUMP STATION, CONTRACTOR SHALL PROVIDE OWNER WITH THE FOLLOWING: a. OPERATION AND MAINTENANCE MANUALS.
- b. ONE-YEAR WARRANTY ON ALL STRUCTURES, PUMP STATION MECHANICS
- AND ELECTRIC COMPONENTS, ALL PIPING AND CONNECTIONS. c. STARTUP REPORT THAT INCLUDES DRAW DOWN TESTS TO DETERMINE
- THE OPERATING POINTS FOR BOTH PUMPS.

PUN	ЛР
PARAMI	ETERS
STATION	I
PUMP	HOMA
MODEL	AMS444-285ASC
IMPELLER	SINGLE CHANNEL
FLOW (GPM)	610
TDH (FT)	99.7
VOLTAGE	230 / 460
HP	34.5
PHASE	1Ø
HERTZ	60
RPM	1750

PUMP STATION SCHEDULE


				Γ	MEASUREME	ENT (FT.)			
PUMP									
STATION	A	В	С	D	E	F	G	Н	
I	177.00	176.50	176.00	175.50	171.33	169.83	188.50	187.83	



I	J	к	
180.93	8.0'	10.5'	


NON-MERCURY

Algorithm	DUMP STATION DETAILS DUMP STATION DETAILS 0F: 0F: 0F: 0F: <	SHA	111X S 000000000000000000000000000000000
PUMP STATION DETAILS PUMP STATION DETAILS PUMP STATION DETAILS OF: PUMP STATION DETAILS OF: Record of the strenge of the str	PUMP STATION DETAILS PUMP STATION DETAILS PUMP STATION DETAILS OF: RECORD OWNER: FREDERICK ROBIE, JR. RECORD OWNER: FREDERICK ROBIE, JR. COBRUCE ROBIE ORDIT LON POLDEN, MAINE RECORD OWNER: FREDERICK ROBIE, JR. COBRUCE ROBIE POLDEN, MAINE OPATIAND, MANE POLDEN, MAINE POLDEN, MAINE PORTIAND, MANE POLDEN, MANE POLDEN, MANE		C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION TO TOWN REV: BY: DATE: STATUS: THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC.
DUMP STATION DETAILS OF: OF: DESIGNED JBP DESIGNED JBP DRAWN MAINE FOR: DATE DOBIE STREET CHECKED JBP DRAWN STI CHECKED SMF DATE 05/31/2022 SCALE NTS DORTAND, MAINE DORTAND, MAINE DORTAND, MAINE	DUMP STATION DETAILS OF: OF: DESIGNED STREET SUBDIVISION OF: DESIGNED JBP DRAWN MAINE FOR: DATE 05/31/2022 SCALE NTS DATE 05/31/2022 SCALE NTS DATE 05/31/2022 SCALE NTS DATE 05/31/2022 SCALE NTS DATE 05/31/2022		South Portland, ME 04106 Tel. 207-200-2100
DESIGNEDJBPDRAWNSTICHECKEDSMFDATE05/31/2022SCALENTSPROJECT21483	DESIGNEDJBPDRAWNSTICHECKEDSMFDATE05/31/2022SCALENTSPROJECT21483		•
DRAWNSTICHECKEDSMFDATE05/31/2022SCALENTSPROJECT21483	DRAWNSTICHECKEDSMFDATE05/31/2022SCALENTSPROJECT21483		PUMP STATION DETAILS OF: ROBIE STREET SUBDIVISIO ROBIE STREET SUBDIVISIO ROBIE STREET GORHAM, MAINE FOR: FOR: FOR: FOR: FOR: FOR: FOR: FOR:
DATE 05/31/2022 SCALE NTS PROJECT 21483	DATE 05/31/2022 SCALE NTS PROJECT 21483		DRAWN STI
PROJECT 21483	PROJECT 21483		DATE 05/31/2022
SHEET27 OF29	SHEET27 OF29		



- LINK-SEAL ASSEMBLY WITH SST BOLTS AND NUTS · /4 v NEW WALL/FLOOR

PIPE PENETRATION DETAIL



H.I. HURRICANE CLIP

@ EACH TRUSS

1" x 3" PINE STRAPPING

└── 1/2" EXTERIOR A-C

GRADE PLYWOOD

- 1" x 4" WOOD TRIM

- 1/2" EXTERIOR A-C

GRADE PLYWOOD

ALL AROUND

DIRECTION

SILL SEAL

---- (2) #4'S CONT.

- 2" RIGID INSULATION

ا فا •

NOT TO SCALE

TYPICAL WALL SECTION

- 6" CONCRETE SLAB

PITCHED TOWARDS

FLOOR DRAIN FROM EACH WALL

- COMPACTED STRUCTURAL FILL

— #4 @ 12" O.C. E.W. AT < OF WALL

— #4 @ 12" O.C. W/STD. HOOK, LAP 1'-6"

FROM TOP-PROVIDE CONTRACTION CONTROL JOINTS AT MID SLAB EACH

- PREMOLDED EXT. JT.

BUILDING DESIGN TO MEET ALL LOCAL AND STATE IBC (INTERNATIONAL BUILDING CODE) BUILDING CODES.
<u>WOOD FRAMING:</u> A. ALL WOOD FRAMING FASTENING SHALL BE IN ACCORDANCE WITH THE 2003 IBC, UNLESS NOTED OTHERWISE.
B. ALL WOOD FRAMING AND STUDS TO BE #2 GRADE SPF OR BETTER, KILN DRIED TO 19% MAXIMUM MOISTURE CONTEN WITH THE FOLLOWING BASE DESIGN VALUES:
EXTREME FIBER IN BENDING, REPETITIVE MEMBER USE,Fb=750 PSIHORIZONTAL SHEAR,Fv=130 PSICOMPRESSION PARALLEL TO GRAIN,Fc=1000 PSIMODULUS OF ELASTICITY,E=1,100,000 PSI
C. ALL TRUSSES TO BE PRE-ENGINEERED AND FABRICATED IN A TPI APPROVED PLANS. SUBMIT STATE OF MAINE P.E. STAMPED SHOP DRAWINGS WITH CALCULATIONS FOR REVIEW PRIOR TO FABRICATION.
D. BRACE ALL TRUSSES IN ACCORDANCE WITH SHOP DRAWINGS AND LATEST TPI STANDARDS.
<u>CONCRETE:</u> A. ALL CONCRETE WORK SHALL CONFORM TO ACI 318, LATEST EDITION.
B. CONCRETE STRENGTH, fc, 28 DAYS SHALL BE: 3000 PSI FOR FOOTINGS AND WALLS 3000 PSI FOR SLAB
C. ALL WALL AND FOOTING CONCRETE SHALL HAVE 4-6% ENTRAINED AIR, ASTM C-260. SLABS TO HAVE NO ENTRAINED AIR.
D. REINFORCING: ASTM A-615, GRADE 60, NEW DEFORMED BARS.
E. WELDED WIRE FABRIC: ASTM A-185 FLAT SHEETS ON CONCRETE BRICK SUPPORTS AT 3'-0" O.C. EACH WAY.
F. CONCRETE MATERIALS: PORTLAND CEMENT: ASTM C-150 TYPE I OR II NORMAL WEIGHT AGGREGATE: ASTM C-33, MAX SIZE ¾"
DOORS: A. DOORS: 1-¾" THICK, 18 GAUGE STEEL, FLUSH INSULATED STEEL DOORS STEEL FRAME AS MANUFACTURED BY STEEL-CRAFT OR EQUAL.
B. HARDWARE: 3 PR. FULL MORTISE STAINLESS STEEL HINGES WITH NON-RISING PINS, BORED LOCKSET, DOOR CLOSEF WEATHER STRIPPING JAMBS AND HEADS AND THRESHOLD.
C. ATTIC HATCH: PROVIDE 2' BY 3' CEILING OPENING AND HATCH FOR ATTIC ACCESS.
FINISH: A. EXTERIOR OF BUILDING TO BE VINYL SIDED. COLOR TO BE WHITE OR MEDIUM GRAY.
B. DOORS: TWO(2) COATINGS OF GLIDDEN ALKYD INDUSTRIAL ENAMEL - SERIES 4500 COLOR TO BE SELECTED BY PORTLAND WATER DISTRICT.
C. INTERIOR: TWO(2) COATINGS OF GLIDDEN ALKYD INDUSTRIAL ENAMEL - SERIES 4500 COLOR TO BE SELECTED BY PORTLAND WATER DISTRICT.
D. SURFACE PREPARATION: SHALL BE IN ACCORDANCE WITH MANUFACTURER RECOMMENDATIONS AND REQUIREMENTS.
ROOFING: A. SHINGLES SHALL BE MINERAL FIBERGLASS REINFORCED, GRANULE-SURFACED ASPHALT, SELF-SEALING,

 <u>ROOFING:</u>
 A. SHINGLES SHALL BE MINERAL FIBERGLASS REINFORCED, GRANULE-SURFACED ASPHALT, SELF-SEALING, CONFORMING TO ASTM D3462. SHINGLES SHALL BE WARRANTED BY MANUFACTURER FOR MINIMUM OF 25 YEARS. SHINGLE COLOR SHALL BE SELECTED BY PORTLAND WATER DISTRICT.

B. UNDERLAYMENT SHALL BE 15 POUND, ASPHALT-SATURATED FELT CONFORMING TO ASTM D226, TYPE I, WITHOUT PERFORATIONS AND SPECIFIED BY THE SHINGLE MANUFACTURER FOR USE AS UNDERLAYMENT.

C. ICE AND WATER SHIELD SHALL BE INSTALLED ALONG THE FIRST SIX FEET OF THE ROOF, AT ALL EDGES.

MAP	27	LOT	20		
MAP	25	LOT	8		
MAP	24	LOT	20	&	19

SHAWN M. FRANK, PE 6396	СССТАТИ ОГ СТАТИ ПОТИТИТИТИТИТИТИТИТИТИТИТИТИТИТИТИТИТИТИ
	C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW C SMF 12-21-2023 SUBMISSION TO DEP FOR STORMWATER LAW B SMF 11-13-2023 PRELIMINARY SUBDIVISION COMMENT RESPONSE SUBMISSION A SMF 08-21-2023 PRELIMINARY SUBDIVISION PLAN SUBMISSION TO TOWN REV: BY: DATE: STATUS: THIS PLAN SHALL NOT BE MODIFIED WITHOUT WRITTEN PERMISSION FROM SEBAGO TECHNICS, INC. ANY ALTERATIONS, AUTHORIZED OR OTHERWISE, SHALL BE AT THE USER'S SOLE RISK AND WITHOUT LIABILITY TO SEBAGO TECHNICS. INC.
	TE CHNCSCOM 75 John Roberts Rd. 8uite 4A South Portland, ME 04106 Tel. 207-200-2100
	G DETAILS SION RECORD OWNER: FREDERICK ROBIE, JR. C/O BRUCE ROBIE 32 BEECHNUT LANE HOLDEN, ME
	PUMP STATION BUILDING DETAILS oF: ROBIE STREET SUBDIVISION ROBIE STREET GORHAM, MAINE FOR: FOR: FOR: FOR: FOR: FOR: FOR: FOR:
	DESIGNED JBP DRAWN STI CHECKED SMF DATE 05/31/2022 SCALE NTS PROJECT 21483 SHEET28 OF29

